

Purefoam Insulation LLC.

6919 Benson Rd
Shelbyville, KY 40065

SPENCER CO. PUBLIC SCHOOLS
JIM OLIVER
520 TAYLORSVILLE RD.
TAYLORSVILLE KY, 40071

FEBRUARY 21, 2014

PROPOSAL
HILLVIEW ACADEMY ROOF RECOAT
404 MAIN CROSS
TAYLORSVILLE, KY

SCOPE OF WORK:

1. POWER WAS ROOF TO REMOVE DIRT AND DEBRIS.
2. TEAR OUT ALL SATURATED FOAM AREAS AND SPRAY APPLY NEW POLYURETHANE FOAM.
3. APPLY SILICONE BASE COAT OVER ALL REPAIRED AREAS.
4. REPAIR ALL OTHER ROOF DAMAGE WITH SILICONE CAULK.
5. SPRAY APPLY TOP COAT OF SILICONE COATING OVER THE ENTIRE ROOF SECTION INCLUDING UP PARAPET WALLS (FINAL COLOR TO BE LIGHT GREY).
6. CLEAN UP ALL TRASH AND DEBRIS AND REMOVE FROM PROPERTY.

NOTE: *500 SQ. FT. OF TEAR OUT IS INCLUDED IN THIS PRICE. ANY ADDITIONAL TEAR OUT WILL BE AN ADDITIONAL \$2.35 A SQ. FT.*

WARRANTY: PROVIDE OWNER WITH A 10-YEAR NO LEAK WARRANTY.

COST: \$13,880.00

TERMS: DUE UPON COMPLETION

RESPECTFULLY SUBMITTED,
MANUEL ADLER

TO ACCEPT THE SCOPE OF WORK, COST AND TERMS ABOVE PLEASE SIGN
BELOW AND FAX BACK TO (502)220-4391

SIGNATURE _____

DATE _____