# **AIA** Document G701° – 2017

# Change Order

PROJECT: (Name and address)	CONTRACT INFORMATION:	CHANGE ORDER INFORMATION:
Hopkins County Auxiliary Gym Additions to Existing High Schools	Contract For: General Construction	Change Order Number: 001
to Existing Then Schools	Date: March 20, 2023	Date: July 31, 2023
<b>OWNER:</b> (Name and address)	<b>ARCHITECT:</b> (Name and address)	<b>CONTRACTOR:</b> (Name and address)
Hopkins County Board of Education	Sherman Carter Barnhart Architects PLLC	Danco Construction
230 South Seminary Street	144 Turner Commons Way	3201 Interstate Drive
Madisonville, KY 42431	Suite 110	Evansville, IN 47715
	Lexington, KY 40508	

#### THE CONTRACT IS CHANGED AS FOLLOWS:

(Insert a detailed description of the change and, if applicable, attach or reference specific exhibits. Also include agreed upon adjustments attributable to executed Construction Change Directives.)

Remediate light-weight traffic access road and parking area that yielded excessive pumping and rutting. Remediation will be done in accordance with American Engineer's report conducted on 7/13/23.

The original Contract Sum was	\$ 9,011,590.00
The net change by previously authorized Change Orders	\$ 0.00
The Contract Sum prior to this Change Order was	\$ 9,011,590.00
The Contract Sum will be increased by this Change Order in the amount of	\$ 41,950.00
The new Contract Sum including this Change Order will be	\$ 9,053,540.00

The Contract Time will be increased by Zero (0) days. The new date of Substantial Completion will be

**NOTE:** This Change Order does not include adjustments to the Contract Sum or Guaranteed Maximum Price, or the Contract Time, that have been authorized by Construction Change Directive until the cost and time have been agreed upon by both the Owner and Contractor, in which case a Change Order is executed to supersede the Construction Change Directive.

#### NOT VALID UNTIL SIGNED BY THE ARCHITECT, CONTRACTOR AND OWNER.

Sherman Carter Barnhart Architects PLLC	Danco Construction	Hopkins County Board of Education
ARCHITECT (Firm name)	CONTRACTOR (Firm name)	OWNER (Firm name)
Christopher-Bornhum James		
SIGNATURE	SIGNATURE	SIGNATURE
Chris Jones, Associate Principal		
PRINTED NAME AND TITLE	PRINTED NAME AND TITLE	PRINTED NAME AND TITLE
July 31, 2023		
DATE	DATE	DATE

1

# FACPAC Contract Change Order Supplemental Information Form (Ref# 58356)

Form Status: Saved

Tier 2 Project: High School Auxiliary GymsBG Number: 22-408Status: ActivePhas

District: Hopkins County (HB678) Phase: Project Initiation (View Checklist)

Contract: Danco Construction, Inc. , 0001, General Construction Type: General Contractor Proposed

Change Order Number	1
Time Extension Required	No
Date Of Change Order	7/31/2023
Change Order Amount To Date	Increase

## **Construction Contingency**

Calculations below are project wide. Remaining negative Construction Contingency may require the submission of a revised BG1.

Current Approved Amount	\$711,050.00			
Net Approved COs	\$0.00			
Remaining After Approved COs	\$711,050.00			
Net All COs	\$41,950.00			
Remaining After All COs	\$669,100.00			
This Requested Change Order Amount \$41,950.00				
Change In A/E Fee This Change Order \$2,370.17 +/-				

Change In CM Fee This Change Order

+/-

Remaining Construction Contingency

Balance

Contract Change Requested By General Contractor

Contract Change Reason Code Site Conditions

Change Order Description And Justification

Remediate light-weight traffic access road and parking area that yielded excessive pumping and rutting. Remediation will be done in accordance with American Engineer's report conducted on 7/13/23.

Cost Benefit To Owner Cost is fair and reasonable. Contract unit prices have been utilized Yes to support the cost associated with this change order.

## **Detailed Cost Breakdown**

Contract unit prices have not been utilized, provide a detailed cost breakdown which separates labor, material, profit and overhead.

Detail Item	Amount	<b>Percent of Total</b>
Labor	\$18,798.75	44.81%
Materials	\$17,680.00	42.15%
Profit and Overhead	\$5,471.25	13.04%
Bond Insurance		0.00%
<b>Cost Breakdown Total:</b>	\$41,950.00	
Cost for this Change Order supported No		
by an alternate bid or competitive price		
quote		
Explain Why		
1 5		

Change Order Supplemental Informa Page (Online Form Ref# 58356)	ntion Form Signature
Onistophen- Borenhum James	7/31/23
Architect	Date
N/A	
Construction Manager	Date
Finance Officer	Date
Local Board of Education Designee	Date



Monday, July 24, 2023

- To: Sherman Carter Barnhart Architects 107 S 5<sup>th</sup> Street, Paducah, KY 42001
- Attn: Chris Jones

Re: Change Order Request 001 Hopkins County Auxiliary Gymnasiums

To Whom it May Concern,

Danco Construction, Inc. submits the following change order request proposal to provide the work described below:

#### Scope of Work

Remediate light-weight traffic access road and parking area that yielded excessive pumping and rutting. Remediation will be done in accordance with American Engineer's report conducted on 07/13/2023.

#### Cost Breakdown

#### SUBCONTRACTORS

Smiley Excavating	\$36,478.75
OH/MARK-UP:	\$ 5,471.25
TOTAL:	\$41,950.00

#### Attachments

- 1) Subcontract Quote Back-up
- 2) AEI Field Report, dated July 13, 2023.

Please contact me with any questions.

aniel a. Greenwood.

David Greenwood Estimator / Project Manager

32 East Broadway Madisonville, KY 42431 PH. (270) 825 - 1472



DATE:	18-Jul-23	Request for Change Order		
PROJECT:	Hopkins Co Aux Gyms		SE Project #:	23-101
GC:	Danco		COR #	2

Subject: Unsuitable Subgrade Material Remediation at Madisonville North Hopkins High School per Attached AEI Report


#### Change Order Quote

Description	Unit	Est. QTY	Unit Cost		Total
Excavate and Remove Unsuitable Spoils	CY	790.00	\$ 9.00		\$ 7,110.00
6 oz Geotextile Fabric Install with labor	SF	23,500.00	\$ 0.18		\$ 4,230.00
Stone Haul and Placement	TN	1,105.00	\$ 6.75		\$ 7,458.75
#2 Stone	TN	1,105.00	\$ 16.00		\$ 17,680.00
			Change Order	TOTAL	\$ 36,478.75

nange Order TOT Ş

Prepared By:

Jake Smiley





Project Name: Madison North Hopkins HS & Hopkins County Central HS Project Number: 222-339 Project Phase: Testing & Special Inspections Weather: Cloudy / 80°F Contractor: Danco Date: 07-13-2023

#### **Description of Observations / Testing performed:**

American Engineers was on site for testing and special inspections. While on site the following observations were made:

- A sub grade review was conducted on the proposed new Gymnasium building addition at the Madison North Hopkins High School today.
- The subgrade material within the building pad footprint had been compacted utilizing a sheep's foot compactor and a smooth drum vibratory roller.
- Approximately 1.9 feet of compacted fill was placed in compacted lifts to achieve the building pad sub grade elevation.
- A loaded tri-axle dump truck was utilized to conduct proof roll testing on the subgrade.
- The proof roll yielded little to no sign of pumping and or movement under stress of the loaded truck within the building addition footprint.
- The proposed new light weight traffic access road and parking area along the back side of the proposed building addition received a proof roll and yielded excessive pumping and rutting under the stress of the loaded truck.
- Test pits were excavated within the roadway areas exhibiting excessive pumping and rutting.
- 1<sup>st</sup> test pit located near southern corner of the proposed addition at the existing asphalt yielded six to eight feet of dark gray to brown unsuitable material before what appears to be suitable material.
- 2<sup>nd</sup> test pit located near northwest corner of the proposed building addition within the roadway and yielded two feet of dark gray to brown unsuitable material before what appears to be suitable material.
- The contractor was notified of the observations made onsite. American Engineers, Inc. offers the following recommendations:
  - The unsuitable areas should be undercut two feet from the existing ground surface and backfilled with No. 2 stone wrapped in geotextile fabric.
  - An AEI representative should be onsite to monitor remediation efforts.
- The approximate areas of unsuitable subgrade material are shown in Figure 1 below.





## Figure 1: Approximate Area of Unsuitable Subgrade Material

Inspector: Thomas Ervin Starting time: 5:00 AM Ending time: 3:00 PM



Project Name: Madison North Hopkins HS & Hopkins County Central HS Project Number: 222-339 Project Phase: Testing & Special Inspections Weather: Cloudy / 80°F Contractor: Danco Date: 07-13-2023

#### **Description of Observations / Testing performed:**

American Engineers was on site for testing and special inspections. While on site the following observations were made:

- A sub grade review was conducted on the proposed new Gymnasium building addition at the Madison North Hopkins High School today.
- The subgrade material within the building pad footprint had been compacted utilizing a sheep's foot compactor and a smooth drum vibratory roller.
- Approximately 1.9 feet of compacted fill was placed in compacted lifts to achieve the building pad sub grade elevation.
- A loaded tri-axle dump truck was utilized to conduct proof roll testing on the subgrade.
- The proof roll yielded little to no sign of pumping and or movement under stress of the loaded truck within the building addition footprint.
- The proposed new light weight traffic access road and parking area along the back side of the proposed building addition received a proof roll and yielded excessive pumping and rutting under the stress of the loaded truck.
- Test pits were excavated within the roadway areas exhibiting excessive pumping and rutting.
- 1<sup>st</sup> test pit located near southern corner of the proposed addition at the existing asphalt yielded six to eight feet of dark gray to brown unsuitable material before what appears to be suitable material.
- 2<sup>nd</sup> test pit located near northwest corner of the proposed building addition within the roadway and yielded two feet of dark gray to brown unsuitable material before what appears to be suitable material.
- The contractor was notified of the observations made onsite. American Engineers, Inc. offers the following recommendations:
  - The unsuitable areas should be undercut two feet from the existing ground surface and backfilled with No. 2 stone wrapped in geotextile fabric.
  - An AEI representative should be onsite to monitor remediation efforts.
- The approximate areas of unsuitable subgrade material are shown in Figure 1 below.





## Figure 1: Approximate Area of Unsuitable Subgrade Material

Inspector: Thomas Ervin Starting time: 5:00 AM Ending time: 3:00 PM