| GREGORY |   |   |   |   | j. | V | /IN | M |
|---------|---|---|---|---|----|---|-----|---|
| A       | R | C | Н | ŧ | T  | E | C   | 7 |

# FAXTRANSMITTAL

| To: Gary Milb                        | <b>y</b>  | From:                                     | Greg Winn                              |  |
|--------------------------------------|---|---|--|--|
| Fax: 270-769-8889                    |   |   | (Including Cover) 3                    |  |
| Phone:                               |   | Date:                                     | 20 June 06                             |  |
| Re. Meadow Vi                        | PW  | CC:                                       |  |  |
| X For Review  Gary -                 | Please Comment  | ☐ Please Reply                            | X Per Your Request                     |  |
| Per our conversa<br>breakdown info i | ation today (and my subs<br>from Swift Roofing for th | sequent voice-mail (<br>ne pending Change | to you). I have attached the<br>Order. |  |
|                                      |   |   | the total down to \$30,305             |  |

I realize that there was some impatience over the amount of time that it took to refine this number, but I believe that the outcome was well worth the time spent.

I will be happy to review this information at any time with you or anyone who may want further explaination, 502.445.5667

Thanks.

Gree

2443 BLVD. NAPOLEON LOUISVILLE, KENTUCKY 40205

Phone: 502.445.5667 Fax: 502.479.5974 winn arch@insightbb.com





SWIFT ROOFING OF ETOWN, INC. PO. BOX 802 ELIZABETHTOWN XY 42702 PHONE (270) 737-2224 FAX (270) 737-5307

Attn Grog Winn

6/20/06

Re.: Mosdowview Elem Saddle Replacement

Swift Roofing will provide all labor, material, equipment, supervision and insurance to complete the scope of work listed below

Note. The existing Polystyrene saddles to be reused, would not stand up to the installation of the new TREMCO roof system there was some type of furning phenomena that dissolved the existing saddles. Below is the cost breakdown associated with their replacement.

# Scope of work:

## Includes

Remove existing roof and Tapered Saddles at S.E. Classroom drain line.

2 Justall new Tapered Iso. And rigid Iso insulation overlaid with new 1/2" wood fiber and 14" Dens Deck board.

3 Install new Tremco Roof system making required tie in to adjoining roof area

Install new baseflashing effected by replacement of saddles 4.

5 Remove all debris related to this scope of work.

| Labor                | 5,635 00    |
|----------------------|-------------|
| Material:            | •           |
| 1,000 Fasteners      | 150.00      |
| 12 sq Tapered Iso    | 1,884,00    |
| 19 sq '4" WF         | 383 00      |
| 19 sq. '4" Dens Deck | 655 00      |
| Drain lead, cement & |             |
| misc material        | 185,00      |
| Disposal             | 554.00      |
| Subtotal             | 9,446 00    |
| 10% OHP              | 944 60      |
| Total:               | 4 10 140 60 |

Brian Delk Project Manager

03



#### SWIFT ROOFING OF ETOWN, INC.

P.O. BOX 502 EUZABETHTOWN, KY 42702 PHONE (270) 737-2224 FAX (270) 737-3307

Atto: Greg Winn

6/20/06

Re: Mexdowview Elem Cricket Replacement

Swift Roofing will provide all labor, material, equipment, supervision and insurance to complete the scope of work listed below

# Scope of work

#### Includes

Ì. (1) Roof drain line approx 16" x 148"

Remove existing .060 mil EPDM temporary roof, dens deck, wood fiber and Styrofoam cricket material. Install new 1/2" tapered Iso crickets.

2 (2) Roof drain lines approx. 323 linear feet.

Remove existing Styrofoam cricket material and install new 1/2" tapered Iso crickets.

3. Remove all debris related to this scope of work.

| Labor                  | \$ 8,576,00  |
|------------------------|--------------|
| Material:              |              |
| 1000 Fasteners         | 150,00       |
| 41 sq. Tapered Iso     | 6,437,00     |
| 24 sq. WF              | 484.00       |
| 24 sq. Dens Deck       | 827.00       |
| Cement & misc material | 412.00       |
| Disposal               | 1,218.00     |
| Subtotal:              | \$ 18,104.00 |
| 10% OHP                | \$ 1,810.40  |
| Total:                 | \$ 19,914.40 |

## Note:

Once the new cricket material is in place the finished roof system will be installed as specified.

Brian Delk Project Manager