






1. NOTIFY L.G.E. ELECTRIC DISTRIBUTION DEPARTMENT FOR INSPECTION AFTER PAD IS FORMED AND DUCT IS INSTALLED. BEFORE POURING CONCRETE CALL: 364-8370. MINIMUM 24 HOUR NOTICE REQUIRED.
2. PAD MUST MEET STATE FIRE MARSHAL APPROVAL. FOR LOCATIONS AS IN BULLETIN 11-P-81.
3. PAD MUST BE SUFFICIENTLY REINFORCED TO SUPPORT 17,000 POUNDS.
4. NO MORE THAN EIGHT 4" SECONDARY DUCTS. MAXIMUM OF 8 SETS OF 7500CM OR 8 SETS OF 5000CM SECONDARY CABLES ALLOWED IN TRANS.
5. CUSTOMER TO PROVIDE "AS BUILT" DRAWING OF CENTER LINE OF DUCT, AS DESCRIBED BY USE OF BRASSING AND CALLS.
6. CUSTOMER WILL BE REQUIRED TO INSTALL PIPE PROTECTION OR WINDOWLIDS IF REQ'D BY L.G.E.

CUSTOMER TO INSTALL OR BUILD TRANSFORMER PAD, MINIMUM 15' FROM BUILDING PER DRAWING 42 06 04 E L.G. & E. TO SET A 300 KVA, 12.5 KV, 120/208V PAD MOUNT TRANSFORMER, T.L.M. #5779988

MINIMUM OF 8'-0" FRONT 2'-0" SIDE AND BACK TO ANY OBSTRUCTION OR PLANTINGS



CUSTOMER REQUIREMENTS
PRIMARY DUCT
DUCTS TO BE COMPLY WITH MINIMUM 1/2" THICKNESS AND 1/2" DIA. DUCTS TO BE PVC OR UNPLASTICIZED MATERIAL
SECONDARY CABLES
CUSTOMER SERVICE LIMITED TO 100' IN RISE OF CABLE OVER DUCT. REDUCE DRAINAGE & VIBR. INSTALLATION EXCEEDING ABOVE LIMITATIONS.



CUSTOMER REQUIREMENTS
PRIMARY DUCT
DUCTS TO BE COMPLY WITH MINIMUM 1/2" THICKNESS AND 1/2" DIA. DUCTS TO BE PVC OR UNPLASTICIZED MATERIAL
SECONDARY CABLES
CUSTOMER SERVICE LIMITED TO 100' IN RISE OF CABLE OVER DUCT. REDUCE DRAINAGE & VIBR. INSTALLATION EXCEEDING ABOVE LIMITATIONS.

35' POLE 43824-83442

8510

MINOR LANE ELEMENTARY
8510 MINOR LANE
CIRCUIT SP-1114
OVERHEAD TASK / W.O. 370464
PROJECT CNBCD3400
UNDERGROUND TASK / W.O. 3705465
PROJECT #CNBCD340U

REMOVE
45' POLE 43833-83450
BANK OF 3 - 100KW TRANSFORMERS
TRANSFER DOWN GUYS & STREET
LIGHT SERVICE TO NEW POLE

SET 45' POLE 10145-46960
TRANSFER GUYS & LIGHTING SERVICE TO THIS POLE
FRAME FOR 3 PHASE UNDERGROUND PRIMARY LATERAL
UNDERGROUND CABLE TO BE ON WEST SIDE OF POLE
INSTALL
3 - 7/16KV CUTOUTS W/25 K FUSES
3 - 9KV LIGHTNING ARRESTORS
T.L.M. #5779987

RUN ONE SPAN #4 DUPLEX, 200' +/-

45' POLE 43851-83446

CUSTOMER TO INSTALL 1 - 5" DUCT FROM
WEST SIDE OF POLE TO TRANSFORMER
PAD, 150' +/-
SEE TYPICAL DUCT SECTION & DRAWING
42 08 02 D FOR DETAILS
L.G. & E. TO INSTALL #2 UNDERGROUND PRIMARY
CABLE FROM POLE TO TRANSFORMER

MINORS LANE
SCHOOL

- JOB BRIEFING**
- 1) HAZARD ASSOCIATED WITH THE JOB ☐
 - 2) WORK PROCEDURES INVOLVED ☐
 - 3) SPECIAL PRECAUTIONS ☐
 - 4) PPE/ST/ SOURCE CONTROL ☐
 - 5) PERSONAL PROTECTIVE EQUIPMENT REQUIRED ☐

Signature _____
Date _____

