

Change Order Request

Detailed (with Breakdown of PCOs), Grouped by Each Number

2.2

#0348- Rineyville Elementary School
275 Rineyville School Rd
Rineyville, KY 40162

Project # #0348
Tel: 270-769-0938

WHITTENBERG CONSTRUCTION CO.
Fax: 270-769-0204

Change Order Request: 019

Date: 5/24/2007

To: Larry Gream
PECK FLANNERY GREAM WARREN INC.
112 North Main Street
Elizabethtown, KY 42701

From: Chris Jones
WHITTENBERG CONSTRUCTION CO.
P.O. Box 9429
4774 Allmond Av.
Louisville, KY 40209-9429

Description	Category	Status
Add Shunt Trip Control for HWH # 2		In Review

Reference	Required By	Days Req	Amt Req
MARINE ELECTRIC COR # 10	5/31/2007	0	849

Notes

PCO No	Date	Reference	Amt Prop	Days Req	Category	Reason
019	5/24/2007		849	0	Change Order	Change Condition

Item No	Item Description	Amt Prop	Reference
001	Marine COR # 10 (see attachment)	801	
002	WCC 5%	40	
003	Bond 1%	8	

Approved By:

Signature

Name

Date

Prolog Manager

Printed on: 5/24/2007 Whittenberg

Page 1

Marine Electric Company

JOB Whiffenberg (Chris Jones)

Rineyville Elementary

Add Shunt Trip control For HWH #2

COR #10

ESTIMATE NO. 0048-06

MARINE JOB NO. 1525

ESTIMATED BY MAK

CHECKED BY

APPROVED BY

DATE 5/23/2007

ITEM NO.	DESCRIPTION	MATERIAL	LABOR HRS
1	Material	\$ 211.67	
2	Labor		11
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
NON-PRODUCTIVE LABOR		\$ -	\$ -
HANDLING MATERIAL	0	NON-PRODUCTIVE LABOR	
LAYOUT / SUPERVISION	0	TOTALS	
TRAVEL TIME	0	\$ 211.67	\$ 10.67
OVERTIME	0	AVERAGE LABOR RATE PER HOUR	
TOTAL	0	LABOR COST	
JOB EXPENSE		MATERIAL COST	
BOND 0.009	\$ 6.38	JOB EXPENSE	
TRAILER	\$ -	TOTAL PRIME COST	
EXCAVATION	\$ -	% OVERHEAD 10%	
RIGGING 0%	\$ -	TOTAL NET COST	
PERMIT & INSPECTION FEES	\$ -	SELLING PRICE	
RENTAL EQUIPMENT	\$ -	COR #10 PRICE QUOTED	
TRUCKS	\$ -		
DELIVERIES	\$ -		
TELEPHONE	\$ -		
DRAWINGS	\$ -		
FREIGHT / CARTAGE	\$ -		
KY SALES TAX 6%	\$ 12.70		
TEMPORARY POWER / LIGHT	\$ -		
PAINTING	\$ -		
	\$ -		
	\$ -		
TOTAL	\$ 19.08		



MARINE ELECTRIC CO., INC.

Pricing

Sheet No. _____ of _____ Sheets

Job RINEYVILLE ELEMENTARY

DUE DATE

Work ADD SHUNT TRIP SHUT DOWN FOR HW #2

ESTIMATED BY	PRICED BY	EXTENDED BY	CHECKED BY	DATE	REQUISITION	PROJECT NO.
MAC	MAC	MAC		5/22/07		048-06

V	MATERIAL	QUANTITY	MATERIAL PRICE	PER	DISC	MATERIAL EXTENSION	LABOR UNIT PRICE	PER	LABOR EXTENSION
1	1/2" EMT w G.S.	70'		52	E	3640	88	E	560
2	#14 THHN	210'	9325	M		1958	876	M	184
3	1/2" EMT Conn	2	3775	C		76	68	E	16
4	HOTMAN ENCLOSURE P13	1	7846	E		7846	63	E	63
5	ENCLOSURE SUPPORT	1	5-	E		5-	50	E	50
6	MUSHROOM HEAD P13	1	6947	E		6947	94	E	94
7	HOLE IN WALL	2	1-	E		2-	50	E	100
8						21167			1067
9									
10									
11									
12									
13									
14									
15									
16									
17									
18									
19									
20									
21									
22									
23									
24									
25									
26									
27									
28									
29									
30									
31									
32									
33									
34	MISC. MAT.								

Total This Sheet Transferred To Recap By Initial

MATERIAL

LABOR

05/31/07 THU 23:31 FAX 12706857978

PFGW E

001

WBW Engineering, Inc.CONSULTING ENGINEERS
Mechanical - Electrical

3000 Canton Street, Hopkinsville, KY 42240

Phone: (270) 886-2536 Fax: (270) 885-7978

E-mail: mail@wbwengr.com

Or : office@wbwengr.com

FACSIMILE MESSAGE

TO: PFGW DATE: 5/31/07
ATTN: Larry JOB NO: _____
FROM: Thomas NO. OF SHEETS: 2
SUBJECT: Pineyville - Whittenberg COR #19
COPY TO: _____

MESSAGE:

Larry,I did not show shut-down
switch for water heater #2.Due to large capacity it will
need to be shut down.I agree w/ material list
and cost submitted by
Marine for this item.Thomas

Whittenberg COR #19



PECK FLANNERY GREAM WARREN
ARCHITECTS, LLC

Larry Gream, Architect

RECEIVED

MAY 29 07

May 25, 2007

Thomas Waldron
Waldron Batey & Wade, Inc.
Indian Hills 3000 Building
Hopkinsville, Kentucky 42240

RE: New Rineyville Elementary School
Rineyville, Kentucky
Architect File No: 0508
BG# 05-118

Dear Thomas :

During the monthly construction meeting this week Marine Electric questioned;

On hot water heater # 2; if there was a requirement/need, etc for a shunt trip control.

Attached is COR # 19 in this regard from Marine electric and Whittenberg. Please respond as soon as possible to the need and/or proposal for this item of work.

Sincerely,

Larry Gream

Yes, this water heater is large enough to require an emergency shutdown switch which I did not indicate on bid documents.

WJ3 5/30/07