

Change Order Request

Detailed (with Breakdown of PCOs), Grouped by Each Number

2.4

#0348- Rineyville Elementary School
275 Rineyville School Rd
Rineyville, KY 40162

Project # #0348
Tel: 270-769-0938

WHITTENBERG CONSTRUCTION CO.
Fax: 270-769-0204

Change Order Request: 028

Date: 7/13/2007

To: Larry Gream
PECK FLANNERY GREAM WARREN INC.
112 North Main Street
Elizabethtown, KY 42701

From: Chris Jones
WHITTENBERG CONSTRUCTION CO.
P.O. Box 9429
4774 Allmond Av.
Louisville, KY 40209-9429

Description	Category	Status
Add drywall above ceilings, per PFGW directive dated 5/30/07	Change Order	In Review

Reference	Required By	Days Req	Amt Req
WCC Cost Worksheet dated 7/13/07		0	4,207

Notes

PCO No	Date	Reference	Amt Prop	Days Req	Category	Reason
028	7/13/2007		4,207	0	Change Order	Consultant Directive

Item No	Item Description	Amt Prop	Reference
001	Add Drywall Above Ceiling (see WCC Cost Worksheet dated 7/13/07)	3,622	
002	WCC 15%	543	
003	Bond 1%	42	

Approved By:

Signature

Name

Date

Prolog Manager

Printed on: 7/13/2007 Whittenberg

Page 1

7/13/2007

Cost Worksheet

PROJECT: Rineyville Elementary									
PROJECT # 348									
OWNER: Hardin Co. Board of Education									
ARCHITECT: Pack Flannery Gream Warren									
C.O.R. # 28									
DESCRIPTION: Addition of Drywall Above Ceilings, per PFGW directive dated 5/30/07									
DESCRIPTION	QTY	U/M	LABOR UNIT	MAT'L./EQUIP. UNIT	SUB. UNIT	LABOR EXTENSION	MAT'L./EQUIP. EXTENSION	SUB EXTENSION	LINE TOTAL
Superintendent (B. Miller)	11.5	HR	\$ 50.07	\$	\$	\$ 575.81	\$	\$	\$ 575.81
Carpenter (C. Riaky)	33	HR	\$ 37.94	\$	\$	\$ 1,252.02	\$	\$	\$ 1,252.02
Carpenter Apprentice (K. Davis)	32	HR	\$ 22.94	\$	\$	\$ 734.08	\$	\$	\$ 734.08
Laborer (S. Shultz)	13.5	HR	\$ 29.46	\$	\$	\$ 397.71	\$	\$	\$ 397.71
RSC Equipment Rental (Baker Scaffold Rental)	1	LS	\$	\$ 189.39	\$	\$	\$ 189.39	\$	\$ 189.39
Metro Materials (Firecode Drywall & Screws)	1	LS	\$	\$ 355.18	\$	\$	\$ 355.18	\$	\$ 355.18
Metro Materials (Firecode Drywall)	1	LS	\$	\$ 107.52	\$	\$	\$ 107.52	\$	\$ 107.52
			\$	\$	\$	\$	\$	\$	\$
		LS	\$	\$	\$	\$	\$	\$	\$
ADDITIONAL FREIGHT									
			LABOR SUBTOTAL			\$ 2,959.62			
			LABOR BURDEN		0%	\$			
			TOTAL LABOR w/ BURDEN			\$ 2,959.62			
			TOTAL MATERIAL/EQUIPMENT/FREIGHT				\$ 662.08		
			TOTAL SUBCONTRACT				\$		
			SUBTOTAL L+M+S						\$ 3,621.71
			SAFETY		0%				\$
			SMALL TOOLS & SUPPLIES		0%				\$
			SUBTOTAL						\$ 3,621.71
			OVERHEAD & MARK-UP		15%				\$ 543.26
			SUBTOTAL w/ O & P						\$ 4,164.96
			BOND		1%				\$ 41.65
			TOTAL CHANGE COST						\$ 4,206.61



**PECK FLANNERY GREAM WARREN
ARCHITECTS, LLC**

Larry Gream, Architect

May 30, 2007

Chris Jones
Whittenberg Construction Company
P. O. Box 9429
Louisville, Kentucky 40209-9429

RE: New Rineyville Elementary School
Rineyville, Kentucky
Architect File No: 0508
BG# 05-116

Dear Chris:

Please provide at time and material rates the following additional work :

- > Provide ½" type X drywall at locations where insulation is not covered by drywall on metal stud and drywall walls. No taping or mudding is required.

Please let me know if you have questions relating to this transmittal.

Sincerely,

Larry Gream

c: Gary Milby
David Wyatt
Charlie Jones