

Change Order Request

Detailed (with Breakdown of PCOs), Grouped by Each Number

#0348- Rineyville Elementary School
275 Rineyville School Rd
Rineyville, KY 40162

Project # #0348
Tel: 270-769-0938

WHITTENBERG CONSTRUCTION CO.
Fax: 270-769-0204

Change Order Request: 056

Date: 4/15/2008

To: Larry Gream
PECK FLANNERY GREAM WARREN INC.
112 North Main Street
Elizabethtown, KY 42701

From: Chris Jones
WHITTENBERG CONSTRUCTION CO.
P.O. Box 9429
4774 Allmond Av.
Louisville, KY 40209-9429

Description

Add sprinkler heads, tees, etc above ceilings throughout Area C

Category

Status

In Review

Reference

PFGW letter dated 3/26/08.

Required By

Days Req

0

Amt Req

13,125

Notes

PCO No	Date	Reference	Amt Prop	Days Req	Category	Reason
Description	Notes					
056	4/15/2008		13,125	0	Change Order	Consultant Directive

Item No	Item Description	Amt Prop	Reference
001	Add sprinkler heads throughout Area C (see Dalmatian quote dated 4/15/08)	12,376	
002	WCC 5%	619	
003	Bond 1%	130	

Approved By:

Signature _____

Name _____

Date _____

Prolog Manager

Printed on: 4/15/2008 Whittenberg

Page 1

Dalmatian Fire, Inc.

Louisville, KY (502)-267-5511

Change Proposal

Job Name:	Rineyville Elementary School	Date: 4/15/08
Customer:	Whittenburg Construction	Arch. Ref:
		RFP#
Attn:	Chris Jones	Dalmatian Field Work Order #

Description of Work:

Additional heads needed above ceiling to accommodate for combustible material above the ceiling.

Quantity	Material	Price	Extended	Hours	Field Labor	Rate	Extended
50	Standard Upright	\$9.65	\$482.50	117	Sprinkler Fitter	\$52.41	\$6,131.97
44	Extend Cov. Upright	\$28.54	\$1,255.76		Sprinkler Fitter x 1.5	\$71.56	
50	1/2" CI Reducers	\$6.25	\$312.50		Sprinkler Fitter x 2	\$90.72	
44	3/4" CI Reducers	\$10.95	\$481.80	6	Supervision	\$63.26	\$379.56
94	1" CI Tee	\$5.32	\$500.08		Field Labor Total		\$6,511.53
282	1" Blk. Pipe	\$2.93	\$826.26				
94	1" Hanger Assembly	\$6.51	\$611.94	Hours	Office Labor	Rate	Extended
					Designer	\$60.00	
					Project Manager	\$75.00	
					Office Labor Total		
				Quantity	Equipment Rental	Rate	Extended
					Power Machine	\$40.00	
					Rental Subtotal		
				6%	Sales Tax		
					Rental Total		
	Material Sub Total		\$4,470.84				
6%	Sales Tax		\$268.25		SUBTOTAL		
	Material Total		\$4,739.09		Material Total		\$4,739.09
Quantity	Subcontracts	Amount	Extended		Field Labor Total		\$6,511.53
					Office Labor Total		
					Rental Total		
	Subcontract Subtotal				Subtotal		\$11,250.62
15%	Profit				10% Overhead/Profit		\$1,125.06
	Subcontract Total				Subcontractor Total		
Dalmatian Fire, Inc. offers a contract add of \$12,376.00					TOTAL		\$12,376.00

Dalmatian Fire, Inc. offers a contract add of \$12,376.00

for the above described changes to our scope.

We trust this is as requested.

Best regards,

Sea Hawk

Sean Kravitz - Project Designer

Breakout

Material	\$5,213
Labor	\$7,163
Total	<u>\$12,376</u>

4/15/2008




**PECK FLANNERY GREAM WARREN
ARCHITECTS, LLC**

Larry Gream, Architect

March 26, 2008

Chris Jones
Whittenberg Construction Company
P. O. Box 9429
Louisville, Kentucky 40209-9429



RE: New Rineyville Elementary School
Rineyville, Kentucky
Architect File No: 0508
BG# 05-116

Dear Chris:

I have reviewed the form material used in the existing classroom building in response to your March 24th email. Due to the fact that this material burns I believe we will need to sprinkle above the ceilings at these locations.

Please forward a proposal to add additional sprinkler heads above ceilings in these areas.

Sincerely,

Larry Gream

c: Gary Milby
David Wyatt
Nami Nahid