

ATTN: LARRY HAMMOND
GALLATIN COUNTY SCHOOLS

QUOTATION NO.: 40975

REVISION:

PHONE: (859) 567-1820

DATE: 10/10/2017

FAX:

Page 1 of 1

WARSAW, KY

REFERENCE: FIREGUARDS

We appreciate this opportunity to submit for your approval and acceptance, this quotation on the following products:

ITEM	QTY	ITEM DESCRIPTION	UNIT PRICE	TOTAL
1	1	550 GALLON CYLINDRICAL HORIZONTAL FIREGUARD THERMALLY INSULATED ABOVEGROUND STORAGE TANK: PRIMARY TANK DIMENSIONS ARE 48" DIAMETER X 72" LONG. SECONDARY TANK DIMENSIONS ARE 60" DIAMETER X 84" LONG. BOTH THE PRIMARY AND SECONDARY TANK TO BE FABRICATED FROM 10 GAUGE A1011 CARBON STEEL. THE INTERSTITIAL AREA OF THE TANK HAS A MONOLITHIC CEMENTIOUS INSULATION INSTALLED TO MINIMIZE HEAT TRANSFER FROM THE SECONDARY TANK TO THE PRIMARY TANK. PRIMARY TANK OPENINGS INCLUDE 1-4" M.N.P.T., 1-4" F.N.P.T., AND 4-2" F.N.P.T. ALONG THE TOP CENTERLINE OF THE TANK. SECONDARY TANK OPENINGS INCLUDE 1-6" M.N.P.T., 1-4" F.N.P.T. INSULATION INSPECTION PORT WITH A P.V.C. PLUG INSTALLED, AND 1-2" F.N.P.T. INTERNAL INTERSTITIAL MONITOR PIPE ALONG THE TOP CENTERLINE OF THE TANK. TANK HAS (2) 6" TALL SUPPORT SADDLES, (2) GROUNDING LUGS, (2) LIFTING LUGS. NO INTERNAL SURFACE PREPARATION, LININGS, OR COATINGS. TANK EXTERIOR TO BE ABRASIVE BLASTED PER S.S.P.C.-SP6 / NACE # 3 SPECIFICATIONS AND SHALL RECEIVE A COAT OF CHEMLINE CHEMTHANE # 3107 ACRYLIC POLYURETHANE, (WHITE) @ 5-6 MILS D.F.T. TANK BUILT IN ACCORDANCE TO U.L.-142, U.L.-2085, AND S.T.I.-F941 STANDARDS AND SPECIFICATIONS AND SHALL BE LABELED AS SUCH.	6,650.00	\$6,650.00
2	1	2000 GALLON CYLINDRICAL HORIZONTAL FIREGUARD THERMALLY INSULATED ABOVEGROUND STORAGE TANK: PRIMARY TANK DIMENSIONS ARE 64" DIAMETER X 12' LONG. SECONDARY TANK DIMENSIONS ARE 70" DIAMETER X 13' LONG. BOTH THE PRIMARY AND SECONDARY TANK TO BE FABRICATED FROM A36 3/16" CARBON STEEL. THE INTERSTITIAL AREA OF THE TANK HAS A MONOLITHIC CEMENTIOUS INSULATION INSTALLED TO MINIMIZE HEAT TRANSFER FROM THE SECONDARY TANK TO THE PRIMARY TANK. PRIMARY TANK OPENINGS INCLUDE 1-6" M.N.P.T., 1-4" F.N.P.T., AND 4-2" F.N.P.T. ALONG THE TOP CENTERLINE OF THE TANK. SECONDARY TANK OPENINGS INCLUDE 1-6" M.N.P.T., 2-4" F.N.P.T. INSULATION INSPECTION PORT WITH A P.V.C. PLUG INSTALLED, AND 1-2" F.N.P.T. INTERNAL INTERSTITIAL MONITOR PIPE ALONG THE TOP CENTERLINE OF THE TANK. TANK EQUIPPED WITH (2) 6" TALL SUPPORT SADDLES, (2) GROUNDING LUGS, (2) LIFTING LUGS. NO INTERNAL SURFACE PREPARATION, LININGS, OR COATINGS. TANK EXTERIOR TO BE ABRASIVE BLASTED PER S.S.P.C.-SP6 / NACE # 3 SPECIFICATIONS AND SHALL RECEIVE A COAT OF CHEMLINE CHEMTHANE # 3107 ACRYLIC POLYURETHANE, (WHITE) @ 5-6 MILS D.F.T. TANK BUILT IN ACCORDANCE TO U.L.-142, U.L.-2085, AND S.T.I.-F941 STANDARDS AND SPECIFICATIONS AND SHALL BE LABELED AS SUCH.	10,975.00	\$10,975.00
3	2	MOR2440 6" 8 OZ EMERGENCY VENT (550 SECONDARY TANK AND 2000 PRIMARY & SECONDARY) ...NOT INSTALLED	114.00	\$228.00
4	1	MOR2440 4" 16 OZ EMERGENCY VENT (GAS PRIMARY TANK) ... NOT INSTALLED	84.00	\$84.00
5	2	STEP UP PLATFORM FOR FILL END	475.00	\$950.00
6	2	STEP AND GRAB HANDLE FOR PUMP END	125.00	\$250.00

AVAILABILITY: ALLOW 5 TO 6 WEEKS AFTER RECEIPT OF APPROVED DRAWINGS

F.O.B. POINT: WARSAW, KY

May we look forward to serving you?

TERMS: NET 30

SOUTHERN Tank & Manufacturing Co., Inc.

ADD SALES TAX IF APPLICABLE

OFFLOADING IS RESPONSIBILITY OF CUSTOMER

CHERIE ACKER, SALES REPRESENTATIVE

***** DISCLAIMER *****

Because the tank, equipment, and piping on your order will be subjected to vibrations and motion during delivery, Southern Tank & Mfg Co, Inc will not be responsible for seepage or leaks at any threaded connections. Piping is tested in our shop at these connections after assembly and prior to shipment to assure there are no leaks or seepage. Southern Tank takes all necessary and reasonable steps to minimize vibrations in transit with the use of bracing. However, we cannot guarantee that seepage will not occur. Re-tightening on site BY OTHERS may be required.

Installation and wiring of equipment is the responsibility of the end user unless otherwise stated in quotation.

SOUTHERN TANK will charge 1-1/2% per month interest on all invoices not paid within 30 days of invoice date.

** QUOTATION WILL BE HONORED FOR 15 DAYS FROM QUOTATION DATE **