

Date: January 19, 2018

Project: Spencer Co High School Baseball  
Taylorsville, KY

## Quotation Price – Materials Delivered to Job Site and Installation

Spencer Co High School Baseball ..... \$342,000

## Light-Structure System with Total Light Control – TLC for LED™ technology

### Guaranteed Lighting Performance

- Guaranteed light levels
- BallTracker™ technology – targeted light, optimizing visibility of the ball in play with no glare in the players typical line-of-sight

### System Description Light-Structure System

- (6) Pre-cast concrete bases with integrated lightning grounding
- (6) Galvanized steel poles
- Factory wired and tested remote electrical component enclosures
- Pole length, factory assembled wire harnesses
- Factory wired poletop luminaire assemblies
- (42) Factory aimed and assembled luminaries, including BallTracker™ luminaires
- UL Listed as a complete system

### Control Systems and Services

- Control-Link® System for remote on/off control and performance monitoring with 24/7 customer support

### Operation and Warranty Services

- Reduction of energy and maintenance costs by 50% to 85% over typical 1500W metal halide equipment
- Product assurance and warranty program that covers materials and onsite labor, eliminating 100% of your maintenance costs for 25 years

**Installation Services Provided** - See attached scope of work

**Payment Terms** - Musco's Credit Department will provide payment terms.

## Delivery Timing

6 - 8 weeks for delivery of materials (LED) to the job site from the time of order, submittal approval, and confirmation of order details including voltage, phase, and pole locations. Due to the built-in custom light control per luminaire, pole locations need to be confirmed prior to production. Changes to pole locations after the product is sent to production could result in additional charges.

## Notes

Quote is based on:

- Shipment of entire project together to one location
- 208 Volt, 3 Phase electrical system requirement
- Structural code and wind speed = 2012 IBC, 115 MPH
- Owner is responsible for getting electrical power to the site, coordination with the utility, and any power company fees
- Includes supply and installation of Musco system including underground wiring and conduit, service entrance panel board, and controls by a licensed contractor.
- Standard soil conditions – rock, bottomless, wet or unsuitable soil may require additional engineering, special installation methods and additional cost
- Confirmation of pole locations prior to production

Thank you for considering Musco for your lighting needs. Please contact me with any questions or if you need additional details.

Curt Mickey  
Musco Sports Lighting, LLC  
Phone: 502-418-6804  
E-mail: [curt.mickey@musco.com](mailto:curt.mickey@musco.com)

