

PROPOSAL

Proposal Submitted To:		Attn:	Today's Date:	
Southgate Independent School District		Greg Duty – Superintendent	Jan. 19, 2019	
Phone Number:	E-Mail:	Job Name:		
859-441-0743	greg.duty@southgate.kyschools.us	Miscellaneous Roof Leak Repairs		
Address, City, State, Zip:		Job Location:		
6 William F. Blatt Ave Southgate, KY. 41071		6 William F. Blatt Ave Southgate, KY. 41071		

Proposed Scope of Work:

Greg,

Thank you for meeting us today to discuss your current roof leak issues. We have developed a repair quote which addresses the immediate leak concerns. We will also develop a budgetary estimate for the full replacement of the roof area in question. The following is our repair scope of work. Please see attached aerial photo showing the repair areas along with photos taken today showing the current leak issues.

- Replace the base flashing along the northeast parapet wall (approximately 25 lineal feet). We will remove the existing metal counter flashing along with the deteriorated base flashing material. Install new base flashing followed by new counter flashing.
- At the gutter edge along the Northwest side of the roof area, we will spud the current gravel away from the gutter edge to expose the deteriorated felts. We will then install new roof stripping plies at the gutter to seal up the failed flashing. The existing gravel will be redistributed.
- On the shingle roof over the auditorium, there is a split in the metal seam at the saddle flashing on the northeast location of the roof. Clean the seam area from any dirt or debris, close the open seam by riveting together. Install a liquid applied flashing with reinforcing fabric over the split seam. Since there are three other identical locations on the same roof, we plan to perform this repair on each to prevent future problems.
- Also, on the shingle roof area, there are small metal saddles that are split, and need replaced. One saddle on the southeast corner and one on the southwest corner. We will remove the shingles and saddle metal and replace the metal with new material and then reinstall the existing shingles.
- There is also some maintenance caulking that needs to be performed in these areas which will be taken care of under this scope.

•	the necessary labor and material to complete the outlined scop			(\$4,845.00)
Payment as Follows:	payment in full - net 30 days			
Any alteration or deviation from All approved extra work will becaud other necessary insurance. Cliability insurance certificate will	as specified in the scope of work. All work to be completed in a substantial workmanlike the above scope of work involving extra cost will be executed only upon written or electrone an added cost to the agreed upon proposal. All agreements contingent upon strikes, Our workers are fully covered by worker's compensation and general liability insurance. It be provided to the owner. If either party commences legal action to enforce its rights put its reasonable actioney's fees and costs of litigation relating to said legal action, as determined to the content of the content	onically transmitted a accidents or delays b Upon contract appro- ursuant to this agreen ermined by a court of Note: 1	approval from the owner or own beyond our control. Owner to co oval, a current worker's compe ment, the prevailing party in sai	ner's representative. carry fire, tornado insation and general d legal chdrawn by us
Acceptance of Proposa	The above prices for the outlined scope(s) of work and conditions are satisfactory and are hereby accepted. You are authorized to do	Signature:		
	the work as specified. Payment will be made as outlined above.	Date:		