

RBS Design Group
723 Harvard Dr.
Owensboro, KY 42301-6185

December 13, 2019

Attn: Jeanie Cannon

Re: Concrete at Front Entrance COR

Jeanie,

Below is the additional cost of labor, equipment, and material to add a concrete approach to the sidewalk at the front of the new main entrance.


Catch Basin Change:

Labor/ Equipment:	\$ 1,814.00
Material:	\$ 1,950.00
Contractor OH & P:	\$ <u>564.60</u>
Total:	\$ 4,328.60

Includes:

- Excavate and remove existing Soil
- Sawcutting and removing asphalt for acceptable transition
- Installing 4" of compacted stone
- Installation of 6x6 WWF and fiber reinforcement
- Place and finish concrete
- Saw cut equally spaced relief joints no more than 10'x10' sections

Respectfully Submitted by,



Brian West

General Estimator/ Project Manager

E-mail: bwest@qands.net

Mobile: (270) 316-6267