

5/7/2020

Mr. Dennis Parrish
Webster County Board of Education
28 SR 1340
Dixon, KY 42409

RE: Foam Roofs (approx. 20,000 sq ft)

WHITE RYNOBOND ROOF SYSTEM

1. The existing roof system will be torn-off to the deck and disposed of. All electrical and mechanical disconnects and under deck disconnects will be by others.
2. Obsolete penetrations and curbs will be removed and new 22 gauge decking or 18 gauge plate will be install over the opening.
3. Two layers of 2.25" (4.5") isocyanurite insulation will be fastened to the deck using Johns Manville High Load fasteners and TPO coated Rynobond plates. Tapered insulation will be installed behind curbs larger than 3'.
4. A single ply of white 60 mil Johns Manville TPO membrane will be laid over the entire roof surface. All seams will be hot air welded.
5. The membrane will be induction welded to the TPO coated plates using the patented Rynobond induction welding system.
6. The outside walls will be flashed with adhered membrane to the front face and new 24 gauge kynar finished copjng will be fabricated and installed.
7. New 24 gauge metal gravel stop will be fabricated and installed
8. New 24 gauge kynar 7" K profile continuous gutter and 3'x4" kynar finished downspouts will be furnished and installed.
9. All remaining curbs will be flashed with adhered membrane and terminated with surface mounted counter flashing or an aluminum termination bar. All remaining pipes will be flashed with preformed TPO boots or field fabricated pipe flashings.
10. 100lf of TPO walkway is included in this quote.

Our price to furnish and install this roofing system is: Base Bid South Roof: \$97,704.00


ADD West Roof: \$92,023.00

Add 1.5% for a 100% performance and payment bond/

A twenty year NO DOLLAR LIMIT Johns Manville labor and material warranty is included.

Sincerely:

David Coudret- President



SWIFT ROOFING, INC.

P.O. BOX 1102
484 INDUSTRIAL ROAD
MURRAY, KY 42071
PHONE (270) 763-5976
FAX (270) 753-8452

5/14/2020

Mr. Dennis Parrish
Webster County Schools
28 SR 1340
Dixon, KY 42409

RE: Urethane foam Roofs (approx. 20,000 sq ft)

WHITE RHINOBOND ROOF SYSTEM

10. The existing roof system will be torn-off to the deck and disposed of. All electrical and mechanical disconnects and under deck disconnects will be by others.
11. Obsolete penetrations and curbs will be removed and new 22 gauge decking or 18 gauge plate will be install over the opening.
12. Two layers of 2.25" (4.5") isocyanurite insulation will be fastened to the deck using heavy duty fasteners and TPO coated Rhinobond plates. Tapered insulation will be installed behind large curbs.
13. A single ply of white 60 mil TPO membrane will be laid over the entire roof surface. All seams will be hot air welded.
14. The membrane will be welded to the TPO coated plates using the patented Rhinobond induction welding system.
15. The outside walls will be flashed with adhered membrane to the front face and new 24 gauge kynar finished copjng will be fabricated and installed.
16. New 24 gauge kynar gutter and 3'x4" kynar finished downspouts will be furnished and installed.
17. All remaining curbs will be flashed with adhered membrane and terminated with an aluminum termination bar. Pipes will be flashed with preformed TPO boots or field fabricated pipe flashings.
18. 100lf of TPO walkway is included in this per request.

Our price to furnish and install this roofing system is: Base Bid South Roof: \$104,900.00

ADD West Roof: \$96,920.00

All electrical and mechanical disconnects and under deck disconnects will be by others.

Add 1.6% for a 100% performance and payment bond/

A twenty year NO DOLLAR LIMIT Manufacturer labor and material warranty is included.

Sincerely:

Steve Williams- Project Manager



MILLER ROOFING CO., INC.

5/15/2020

P.O. BOX 406 - BENTON, KENTUCKY 42025
PHONE: 270-527-1498 • FAX: 270-527-2581

Mr. Dennis Parrish
Webster County School System
28 SR 1340
Dixon, KY

RE: Urethane foam Roofs (approx. 20,000 sq ft)

WHITE RHINO BOND ROOF SYSTEM

10. The existing roof system will be torn-off to the deck and disposed of.
11. Obsolete penetrations and curbs will be removed and new 22 gauge decking or 18 gauge plate will be install over the opening.
12. Two layers of 2" and 2.5" (4.5" total) isocyanurite insulation will be fastened to the deck using heavy duty fasteners and TPO coated Rhinobond plates. Tapered insulation will be installed behind large curbs.
13. A single ply of white 60 mil TPO membrane will be laid over the entire roof surface. All seams will be welded.
14. The membrane will be welded to the TPO coated plates using the patented Rhinobond induction welding system.
15. The outside walls will be flashed with adhered membrane to the front face and new 24 gauge kynar finished copjng will be fabricated and installed.
16. New 24 gauge kynar gutter and 3'x4" kynar finished downspouts will be furnished and installed.
17. All remaining curbs will be flashed with adhered membrane and terminated with an aluminum termination bar. Pipes will be flashed with preformed TPO boots or field fabricated pipe flashings.
18. 100lf of TPO walkway is included in this per request.

Our price to furnish and install this roofing system is: Base Bid South Roof: \$108,400.00

ADD West Roof: \$98,300.00

All electrical and mechanical disconnects and under deck disconnects will be by others.

Add 1.75% for a 100% performance and payment bond/

A twenty year NO DOLLAR LIMIT Manufacturer labor and material warranty is included.

Sincerely:

Kenny Freeman- President

