

Dabney Engineering & Land Surveying

213 East First Street
Campbellsville, Kentucky 42718
Phone: (270) 789-4458

July 31, 2020

Pamela Clements, AIA
Architect
nomi design
1584 Delaware Avenue
Lexington, Kentucky 40505

Re: Topographical Survey proposals
Campbellsville Independent Schools

Attention Ms. Clements,

As you requested, we studied the scope of work for surveying the three athletic field sites; Lady Eagle Softball field Campbellsville Independent Schools Site on Clem Haskins Boulevard, Eagle Football Field and Eagle Baseball Combination Fields Campbellsville Independent Schools Site; Combination fields lie adjacent to Gowdy Street and Bell Avenue.

A topographical survey will be performed; the basis for the coordinate system will be Kentucky Single Zone. Topographical survey will show contours at 1 foot intervals and map aboveground utilities and structures within the limits of the project. Aboveground utilities will be mapped. Public utilities as marked by Kentucky Underground (811) will be mapped. Institutional Subsurface utilities as marked by institution will be mapped. Manholes and subsurface vaults will be measured from aboveground references. No excavations will be made by the surveyor. Institutional drawings, if available, may be referenced for additional information. If further subsurface investigation is required a private utility location service will need to be contracted at additional expense to the location service provider. This service generally cost in the range of \$1200 to \$2000 per site. This topographical survey will not be referenced to any boundary survey and is not intended to be used for the purpose of a boundary survey. If any of the site resides in a FEMA floodplain the flood limits will be approximately delineated on topographical drawing from the FEMA Community Map. Topographical survey will be delivered in paper copies, PDF file and AutoCAD File. Survey will be completed within 4 weeks of the notice to proceed, any inclement weather that prevents field work to proceed or work stoppage may be added to time extension. Owners to provide unrestricted access to facilities within work area.

The site survey limits are described as follows: (See also attached Site Photo Outlines) CIS Softball Turf Project Site on Clem Haskins Boulevard

Softball field topographical survey limits as defined by site photo provided by nomi design (see attached; site contained within the red boundary) and will also include footprint of the dugouts and Concession building, the concrete apron and sidewalks servicing dugouts, concessions and bleacher footprint. First floor elevations will be provided, when applicable.

This location will also be referenced by two set steel stake reference monuments for benchmarks.

Our company proposes to perform the work as outlined for the amount of \$2600.00.

The site survey limits are described as follows: (See also attached Site Photo Outlines) CIS Football-Baseball Turf & Bleacher Project adjacent to Gowdy Street and Bell Avenue

EAGLE Football Field and EAGLE Baseball Combination Fields topographical survey limits as defined by site photo provided by nomi design (see attached; site contained within the red boundary) and will also include footprint of the bleacher, dugouts and Concession building. First floor elevations will be provided, when applicable.

This location will also be referenced by two set steel stake reference monuments for benchmarks.

Our company proposes to perform the work as outlined for the amount of \$4500.00.

We appreciate the opportunity to submit a proposal for the referenced project. Any additional work may be requested at our normal service rates; Field Crew \$105.00 per/hr and P.L.S. \$70 per/hr.

Respectfully Submitted,



Donald A. Dabney, P.L.S

