

### **Alternate Description – West Irvine ESSER II Project**

- **Alternate #1: Filter Rack:** Provide labor, materials, and equipment necessary to provide and install 2" filter racks, 2" MERV rated filters, and duct transitions to the existing unit and existing return air duct as indicated on the drawings and specified. Comply with all contract document requirements.