West Irvine Pavement Improvements

Irvine, Kentucky

for the

Estill County Board of Education

253 Main Street Irvine, Kentucky 40336 p 606.723.2181

BG # 22-178 RTA # 2143



101 old lafayette avenue lexington, kentucky 40502 p 859.254.4018 www.rosstarrant.com

enhancing education through great design

PROJECT SITE ADDRESS:

155 Riverview Rd,
Irvine, Kentucky 40336

Will County Washing Brits Cole Insurance Agency


O'Relly Auto Brits Cole

Automotist store

O'Relly Automotist store

O'Rell

PROJECT VICINITY MAP



rosstarrant
architect
architect

SD0.2 SITE DEMOLITION PLAN

ST IRVINE PAVEMENT IMPROVEMENTS
FOR:

Project No: 2143
Drawn By: KM
Rev'd By: JR/PF

SHEET RELEASE


1
2
3
4
5
6
7
8
COPYRIGHT © 2021
CONSTRUCTION DOCUMENTS

GO.0

COVER SHEET

DATE ISSUED:

JANUARY 13, 2022






2020 LIBERTY ROAD, SUITE 105

STATE OF KENTUCKY ALAN W LEAKE 3032 LICENSED PROFESSIONAL LAND SURVEYOR

12/01/202 APPROVED BY:

PROJECT NUMBER 218097

SHEET NUMBER




GENERAL SITE NOTES


- THE SITE PLANS WERE PREPARED BASED UPON TOPOGRAPHIC SURVEYS BY S&ME, 2020 LIBERTY ROAD, SUITE 105, LEXINGTON, KY 40505, REFER TO SITE SURVEY
- . THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING SITE FEATURES AND CONDITIONS. REPORT ANY DISCREPANCIES TO THE ARCHITECT PRIOR TO THE START OF CONSTRUCTION.
- . THE ARCHITECT AND ARCHITECT'S CONSULTANTS SHALL HAVE NO RESPONSIBILITY FOR THE DISCOVERY, PRESENCE, HANDLING, REMOVAL OR DISPOSAL OF, OR EXPOSURE OF PERSONS TO HAZARDOUS MATERIALS IN ANY FORM AT THE
- POLYCHLORINATED BIPHENYL (PCB) OR OTHER TOXIC SUBSTANCES. 4. THE CONTRACTOR SHALL USE EXTREME CARE IN WORKING AROUND EXISTING

- CONTRACTOR IS TO PROVIDE ALL KPDES PERMITS, NOTICES OF INTENT (NOI'S) AND NOTICES OF TERMINATION INCLUDING EROSION AND SEDIMENT CONTROL PLANS FOR ALL PHASES OF CONSTRUCTION. ALL KPDES AND RELATED DIVISION OF WATER REQUIREMENTS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR UNTIL THE PROJECT IS CLOSED OUT AND THE NOTICE OF
- CONTROLS AT STORM WATER STRUCTURES AND ELSEWHERE ON THE DOCUMENTS ARE NOT TO BE USED FOR DIVISION OF WATER REQUIREMENTS. THESE REFERENCES ARE ONLY REQUIRED BY THE DESIGNER FOR PROPER MAINTENANCE OF THE STORM WATER SYSTEM AND TO MINIMIZE CLEANING OF THE SYSTEM AND PAVEMENTS.

SEDIMENT CONTROL FENCING SHOWN AND REFERENCES TO SEDIMENT

- EXISTING VEGETATION IS TO BE LEFT INTACT UNTIL CONSTRUCTION IN THAT PARTICULAR LOCATION IS REQUIRED. SOIL STABILIZATION PRACTICES (SEEDING, MULCHING, ETC.) ARE TO BEGIN WITHIN 14 DAYS OF PERMANENT COMPLETION OR TEMPORARY HALT (21 DAYS OR MORE) OF WORK IN ANY
- PERIMETER SEDIMENT AND EROSION CONTROLS ARE TO BE INSTALLED PRIOR
- INSTALL SEDIMENT CONTROL FENCE OR SEDIMENT TRAPS AROUND ALL STORM
 - ON THIS SHEET. SEE KDOH STANDARDS FOR INFORMATION CONCERNING
 - EACH RAIN EVENT OF 0.5 INCHES OR MORE, BUT NO LESS THAN ONCE PER
 - PROTECTION PRACTICES AND NOT AS PART OF A BMP PLAN. IF CONSTRUCTION ACTIVITIES PRODUCE CONDITIONS THAT REQUIRE ADDITIONAL CONTROLS, IT IS THE CONTRACTORS RESPONSIBILITY TO
 - ALL STORM DRAINAGE CATCH BASINS, CURB INLETS, AND JUNCTIONS BOXES ARE TO RECEIVE PROTECTION FROM SEDIMENTATION. AT A MINIMUM A PERIMETER SILT FENCE SHOULD BE INSTALLED AROUND THE DRAINAGE





SILT FENCE DETAIL

BMP LEGEND

SEDIMENT CONTROL FENCE. ADDITIONAL FENCE MAY BE REQUIRED AT OTHER AREAS DURING CONSTRUCTION. SEE DETAIL A/SD0.1



-EXISTING GROUND SURFACE

-SAND BAGS TO

SEE NOTE #3

—10 MIL POLYETHYLENE SHEETING

COMPACTED AGGREGATE

(SUCH AS KYDOT#57) TO

SUPPORT CONCRETE PAD

— SWALE OR DITCH TO CARRY

RUNOFF TO A TEMPORARY

— KYTC AGGREGATE NO.2 OR

EQUIVALENT. MIN. 6" DEPTH

SEDIMENT TRAP.

GEOTEXTILE

under stone

CONSTRUCTION DOCUMENTS

Drawn By:

Rev'd By:

SD0.1

INLET SEDIMENT CONTROL.

COPYRIGHT © 2021

22-178

SHEET RELEASE

INTERM

S S

0

NOT FOR

CONSTRUCTION

PROJECT SITE, INCLUDING BUT NOT LIMITED TO ASBESTOS, ASBESTOS PRODUCTS, OVERHEAD AND UNDERGROUND UTILITIES. MEASURES SHOULD BE TAKEN TO PROTECT ALL UTILITIES FROM DAMAGE DURING CONSTRUCTION.

5. SEE EROSION POLLUTION AND SEDIMENT CONTROL PLAN ON SD0.1 FOR RECOMMENDED BEST MANAGEMENT PRACTICES INFORMATION AND SEDIMENT


. REFER TO CONSTRUCTION MANAGER'S PLANS AND SPECIFICATIONS FOR INFORMATION REGARDING CONSTRUCTION SCHEDULE/SEQUENCING, CONSTRUCTION FENCING/STAGING, AND LEED SPECIFIC REQUIREMENTS.

SITE BMP NOTES

TERMINATION APPROVED.

- PARTICULAR AREA.
- TO THE START OF SITE CLEARING AND GRUBBING. EROSION CONTROLS SHALL BE IN ACCORDANCE WITH KENTUCKY DEPARTMENT OF HIGHWAY STANDARDS. CONTROL SHALL BE ACCOMPLISHED BY USE OF INTERCEPTOR DITCHES, DITCH SILT CHECKS, TEMPORARY SEEDING AND OTHER MEASURES AS MAY BE EFFECTIVE IN ACHIEVING THE DESIRED EFFECT. SILT FENCE SHALL BE INSTALLED TO PREVENT EROSION AND WASH-OFF ONTO WALKS, PAVEMENTS AND ALL ADJOINING PROPERTIES.
- PAVED AS APPROVED BY THE ARCHITECT. STORM WATER INLET PROTECTION IS TO BE INSTALLED IMMEDIATELY AFTER INSTALLATION OF THE STRUCTURES. REMOVE PROTECTIONS AT THE COMPLETION OF THE PROJECT WHEN CONDITIONS NO LONGER WARRANT THEIR USE. SEE THIS SHEET FOR DETAILS. TYPICAL SILT FENCE AND SEDIMENT TRAP INSTALLATION DETAILS ARE SHOWN
- THE STONE SILT CHECKS. SEDIMENT CONTROLS ARE TO BE INSPECTED, CLEANED AND REPAIRED AFTER
- WEEK. A LOG OF INSPECTIONS AND CLEANING IS TO BE KEPT ON SITE. THE LOCATIONS OF SEDIMENT CONTROLS SHOWN ARE FOR GENERAL
- PROVIDE, INSTALL AND MAINTAIN THE CONTROLS UNTIL CONDITIONS NO LONGER WARRANT THEIR USE.


STRUCTURE AND INSTALLED UNDER THE GRATE.




SECURE SHEETING -STRAW BALES TYP


SILT CHECK DAM - SEE DETAIL B/SD0.1 CONSTRUCTION ENTRANCE - SEE DETAIL C/SD0.1

DATE ISSUED: JANUARY 13, 2022





JANUARY 13, 2022



GENERAL SITE NOTES

- THE SITE PLANS WERE PREPARED BASED UPON TOPOGRAPHIC SURVEYS BY S&ME, 2020 LIBERTY DRIVE, SUITE 105, LEXINGTON, KY 40505, REFER TO SITE
- SURVEY SHEETS. 2. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING SITE FEATURES AND
 - CONDITIONS. REPORT ANY DISCREPANCIES TO THE ARCHITECT PRIOR TO THE START OF CONSTRUCTION. 3. THE ARCHITECT AND ARCHITECT'S CONSULTANTS SHALL HAVE NO
 - RESPONSIBILITY FOR THE DISCOVERY, PRESENCE, HANDLING, REMOVAL OR DISPOSAL OF, OR EXPOSURE OF PERSONS TO HAZARDOUS MATERIALS IN ANY FORM AT THE PROJECT SITE, INCLUDING BUT NOT LIMITED TO ASBESTOS, ASBESTOS PRODUCTS, POLYCHLORINATED BIPHENYL (PCB) OR OTHER TOXIC SUBSTANCES.
- 4. THE CONTRACTOR SHALL USE EXTREME CARE IN WORKING AROUND EXISTING OVERHEAD AND UNDERGROUND UTILITIES. MEASURES SHOULD BE TAKEN TO PROTECT ALL UTILITIES FROM DAMAGE DURING CONSTRUCTION. SEE EROSION POLLUTION AND SEDIMENT CONTROL PLAN FOR
- RECOMMENDED BEST MANAGEMENT PRACTICES INFORMATION AND SEDIMENT CONTROLS.

SITE GRADING NOTES

- THE CONTRACTOR SHALL VERIFY LOCATIONS AND ACTUAL DEPTHS OF ALL EXISTING STORM DRAINS, GAS MAINS, WATER MAINS, AND PIPES TO ALL NEW CONNECTIONS AND CROSSINGS. CONTRACTOR SHALL PAY PARTICULAR ATTENTION TO AREAS WHERE CONSTRUCTION OR GRADING MAY INTERFERE WITH SUCH LINES.
 - ANY DISCREPANCIES BETWEEN THIS GRADING PLAN AND ACTUAL FIELD CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT IN WRITING PRIOR TO EXCAVATION, GRADING, TRENCHING, OR OTHER CONSTRUCTION OF ANY SORT. FAILURE TO NOTIFY THE ARCHITECT IN WRITING PRIOR TO COMMENCEMENT OF EXCAVATION, GRADING, TRENCHING, OR OTHER CONSTRUCTION SHALL IMPLY THE CONTRACTOR'S VERIFICATION OF AND ACCEPTANCE OF EXISTING SITE CONDITIONS. SAID FAILURE TO NOTIFY THE ARCHITECT IN WRITING SHALL IDENTIFY AND HOLD HARMLESS THE OWNER FROM ANY ADDITIONAL COSTS INCURRED BY THE CONTRACTOR DUE TO DISCREPANCIES NOT REPORTED WHICH COULD HAVE BEEN DETECTED BY PRUDENT AND REASONABLE OBSERVATION AND VERIFICATION BY THE CONTRACTOR.

NOT FOR

CONSTRUCTION

- ALL IMPERVIOUS SURFACES SHALL BE GRADED AND INSTALLED WITH A MINIMUM SLOPE OF ONE PERCENT (1%) AND A MAXIMUM SLOPE OF SEVEN PERCENT (7%)
- 4. ALL PERVIOUS SURFACES SHALL BE GRADED AND INSTALLED WITH A MINIMUM SLOPE OF TWO PERCENT (2 %) AND A MAXIMUM SLOPE OF THIRTY-THREE PERCENT (33%) EXCEPT WHERE SHOWN.
- SLOPE PERVIOUS SURFACES MIN. 5 % AND IMPERVIOUS SURFACES MIN. 1% AWAY FROM BUILDING FOUNDATIONS.
- MAINTAIN GRADING TO PROMOTE POSITIVE DRAINAGE AT ALL TIMES. DO NOT ALLOW WATER TO POND IN CONSTRUCTION AREAS.
- RELOCATE ALL BURIED UTILITIES THAT ARE IMPACTED BY ANY EARTHWORK. RELOCATED UTILITY LOCATIONS ARE TO BE APPROVED BY THE ARCHITECT PRIOR TO STARTING WORK.
- . PROTECT AREAS TO BE SEEDED AS FOLLOWS: A) DITCHES AND DRAINAGE SWALES ARE TO RECEIVE HIGH-VELOCITY EROSION-CONTROL BLANKETS.
- B) SLOPES 4:1 (H:V) OR GREATER ARE TO RECEIVE LONG- TERM EROSION-CONTROL BLANKETS.
- C) SLOPES BETWEEN 4:1 AND 6:1 (H:V) ARE TO RECEIVE SHORT-TERM EROSION CONTROL BLANKETS. D) SLOPES BELOW 6:1 (H:V) ARE TO RECEIVE STRAW
- THE SPECIFICATIONS. DO NOT USE HAY. ANY AREAS DISTURBED DURING CONSTRUCTION ARE TO BE
- RECONDITIONED, SEEDED AND MULCHED PER THE SPECIFICATIONS.
- O. COMPACT SOIL TO NOT LESS THAN THE FOLLOWING PERCENTAGES OF THEIR STANDARD PROCTOR MAXIMUM DRY DENSITY AT PLUS OR MINUS TWO (2) PERCENT OF OPTIMUM MOISTURE CONTENT:
- a) under floor slabs and foundations on STRUCTURAL B) FILLS ON EXISTING SOILS, ROCK CUTS OR SHOT-ROCK FILL - 97% C) PAVED AREAS AND WALKS - 95% D) LANDSCAPE AREAS OUTSIDE MASS FILL AREAS - 85%
- . ALL TREES THAT ARE IDENTIFIED BY THE ARCHITECT TO REMAIN, EITHER ON THE DRAWING OR IN THE FIELD, ARE TO BE PROTECTED IN ACCORDANCE WITH THE SPECIFICATIONS. ALL TREES LOCATED OUTSIDE OF AREAS IDENTIFIED TO BE RE-GRADED ARE TO BE PROTECTED IN ACCORDANCE WITH THE SPECIFICATIONS.
- 2. THE CONTRACTOR SHALL ENSURE THAT CONSTRUCTION DEBRIS AND SEDIMENT ARE REMOVED DAILY FROM SITE DRIVEWAYS, PARKING AREAS, WALKWAYS AND SURROUNDING ROADWAYS AND WALKWAYS.
- B. EXCESS SATISFACTORY SOILS ARE TO BE DISPOSED OF ON-SITE IN A LOCATION IDENTIFIED BY THE OWNER. THESE SOILS ARE TO BE SPREAD AND COMPACTED IN ACCORDANCE WITH THE SPECIFICATIONS.
- 4. THE NEW PARKING, ROADS AND ROAD BASE ARE NOT DESIGNED TO ACCOMMODATE CONSTRUCTION TRAFFIC AND SHOULD NOT BE USED FOR SUCH UNLESS STABILIZED USING #2 CRUSHED STONE AND/OR GEO-GRID IN ADDITION TO THE PAVEMENT DESIGN SECTION SHOWN. IF THE CONTRACTOR WISHES TO USE THE NEW ROAD ALIGNMENTS DURING CONSTRUCTION, IT IS THE CONTRACTORS RESPONSIBILITY TO STABILIZE THE ROAD ALIGNMENT SUBGRADES AND PREVENT THEM FROM BEING
- 5. THE CONTRACTOR SHALL INSTALL AND MAINTAIN A CRUSHED STONE ENTRY AND DRIVE TO REDUCE SOIL TRACKING.

SITE DRAINAGE NOTES

- DRAINAGE PIPE THAT CROSSES UNDER ROADS OR PARKING AREAS SHALL BE REINFORCED CONCRETE. ALL PE PIPE SHALL BE DUAL WALL POLYETHYLENE PIPE WITH SMOOTH INTERIOR WALL, OR EQUIVALENT AS APPROVED IN THE SPECIFICATIONS. ALL STORM PIPING SHALL BE INSTALLED AT A CONSTANT, POSITIVE SLOPE FROM INLET CONNECTION TO DISCHARGED CONNECTION. PIPE SLOPE IS TO BE 0.5% MINIMUM.
- SEDIMENT PROTECTION DEVICES, SUCH AS SILT FENCING SHALL BE INSTALLED IN AND/OR AROUND ALL STORM STRUCTURES.
- EROSION CONTROL BLANKETS ARE TO BE INSTALLED AS INDICATED IN THE SPECIFICATIONS.
- 4. ALL STORM STRUCTURES ARE TO BE DESIGNED FOR H-20 LOADING.
- ALL GRATES AND MANHOLE COVERS ARE TO BE HEAVY DUTY CAST IRON DESIGNED FOR H-20 LOADING.
- ALL ROOF DRAINS AND DOWNSPOUTS, INCLUDING CANOPY DOWNSPOUTS, ARE TO BE PIPED UNDERGROUND AND CONNECTED TO STORM WATER STRUCTURES. DOWNSPOUT BOOT AND DOWNSPOUT SIZES ARE TO BE COORDINATED WITH THE MANUFACTURERS AND INSTALLERS OF EACH ITEM. CLEANOUTS ARE TO BE LOCATED AT EACH CHANGE IN DIRECTION OF THE
- ARE FLUSH WITH THE SURROUNDING SURFACES. THE LOCATIONS SHOWN FOR THE NEW STORM SEWER PIPING AND STRUCTURES ARE APPROXIMATE. ACTUAL LOCATIONS CAN BE ADJUSTED WITH ARCHITECTS BG# WRITTEN APPROVAL IN ORDER TO AVOID UNFORESEEN CONDITIONS OR OTHER Project No: 2143 CONSTRUCTION CONFLICTS. CONTRACTOR IS TO COORDINATE STORM SEWER

PIPING. ENSURE CLEANOUTS ARE DESIGNED FOR AUTOMOBILE TRAFFIC, AND Drawn By: SHEET RELEASE COPYRIGHT © 2021 CONSTRUCTION DOCUMENTS

SITE

ш

BC - BOTTOM OF CURB FFE - FINISHED FLOOR ELEVATION

DRAINAGE LEGEND

SPOT ELEVATION LEGEND

DATE ISSUED: JANUARY 13, 2022

SITE GRADING AND DRAINAGE PLAN

(DS-#) DRAINAGE STRUCTURE. REFER TO STORM DRAINAGE STRUCTURE SCHEDULE.

