



SWIFT ROOFING, INC.

P.O. BOX 1102

MURRAY, KY 42071

PHONE (270) 753-5976

FAX (270) 753-9452

PROPOSAL

DATE:

July 28, 2021

PROPOSAL SUBMITTED TO:

Christian County Schools

200 Glass Avenue

Hopkinsville, KY 42240

JOB NAME AND LOCATION: Pembroke Elementary School.

We hereby submit specifications and estimates for: 2022 Partial Reroofing & Roof Repairs Pembroke Elementary School.

Reroof Areas:

Remove existing roof and insulation down to roof deck.

Mechanically fasten Type II base sheet, install 2 layers of 2" polyisocyanurate, 1/4" tapered saddles, crickets and 1/2" wood fiber coverboard in Type III hot asphalt.

Install Garland modified base sheet in hot asphalt and VersiPly mineral cap sheet in cold applied adhesive.

Restoration Areas:

Remove wet insulation as noted on roof drawing and IR scan. Install new insulation, match existing thickness.

Prime existing roof and flashings with asphalt primer.

Install one mineral surfaced cap flashing ply, install Revitalizer base coat, polyester firm reinforcement, top coat of Revitalizer, let cure, then install reflective coating.

Install new coping cap metal at locations shown on roof drawing.

We propose to furnish material and labor --complete in accordance with above specifications, for the sum of:

***One Million Two Hundred Seventy-Six Thousand Five Hundred Dollars
(\$1,276,500.00)***

All material is guaranteed to be as specified. All work to be completed in a workman like manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents, or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Workman's Compensation Insurance.

Authorized Signature

Danny Swift

Signature _____

Date: _____