

**1532 Russell St.
Covington, KY 41011**

**Phone: 859.291.3159
Fax: 859.581.3022
Mrabe@blaumech.com**

BLAU MECHANICAL INC

November 11, 2022

Rev1 11/22/22

Rev2 12/08/22

Attn. Mr. Eric Neff
Covington Independent Public Schools
25 E 7th St
Covington, KY 41011

RE: Holmes High School Administration Bldg.
Temporary Boiler Option #4

Dear Eric:

We are pleased to offer our proposal to provide a temporary boiler system for a period of (3) months beginning December 9, 2022 at the above referenced building.

This to consist of the following:

- Furnish and install one ADCO MBR100 100HP steam boiler system, trailer mounted (see detailed information next page)
- Pipe, valves and fittings required to connect the temporary unit to the existing system of piping
- Electric and control work
- Provide maintenance and servicing of the system during the rental period
- Labor to complete this installation

This can be performed for the sum of One Hundred Three Thousand Dollars (\$103,000.00). The temporary boiler is available for immediate use, subject to prior rental.

If you should have any questions, please call.

Sincerely,
Joseph Salazar
Joseph Salazar
President

**1532 Russell St.
Covington, KY 41011**

**Phone: 859.291.3159
Fax: 859.581.3022
Mrabe@blaumech.com**

BLAU MECHANICAL INC

Holmes High School
Temporary Boiler

RENTAL BOILER

One (1) ADCO MBR100 HP steam boiler with combination natural gas or No. 2 fuel oil fired "Low NOx" burner, design pressure 150 psi capable of producing 3,450 lbs. steam per hour, complete with gas train, second low water cutoff, pressure controls, flame safeguard, relief valve, feedwater valves, blowdown valves and a fully modulating burner.

Also 1 – Feedwater system
 3 – feedwater pumps
 1 – chemical feed system
 1 – water softener
 1 – blowdown system
 Electrical switch gear – 480V/50-amp service / 3 phase
 1 – main steam stop valve
 1 – operators manual

The unit is pre-piped in a totally enclosed in a semi-trailer

One pressure reducing station with relief valve to flow up to 7405lbs per hour of steam from 125 >15 psi. Comes loose for installation in the header lines once on site.

Trailer will be placed at the side of the building, east of the chimney stack.