

## POST-BID FORM OF PROPOSAL

### ACCEPTED ITEMS

Item	Description	Amount (+/-)
2	Provide cost savings for the deduction of all work associated with specification 32 92 00 – 2.4 Grassy Pavers with allocation provided for seeded lawn area in lieu of grassy paver system.	-\$54,259
3	Provide cost savings for the deduction of all work associated with the seat walls indicated on the drawing identified as “Exhibit A”, attached.	-\$118,700
4	Provide cost savings for the deduction of all work related with specification 32 31 21 Decorative Metal Security Fences and Gates. Work should include but is not limited to the fencing system and foundations at each dumpster location and around the mechanical systems located at the existing field house building.	-\$123,200
6	Provide cost savings for the deduction of all work related to modifying the 2-1/2” designed and bid synthetic turf system as a 2-1/4” synthetic turf system.	-\$34,733.76
7	Provide cost savings for the deduction of the lean clay allowance from the project.	-\$607,500
8	Provide cost savings for the deduction of the topsoil allowance from the project.	-\$425,250
10	Provide cost savings for the deduction of all work related to modifying all areas of the project where sod is denoted (excluding baseball and softball fields) from sod to seed.	-\$40,020
11	Provide cost savings for the deduction of all work related to remove plantings as denoted on Enlarged Plans A and B on C302 with allocation provided for seeded lawn area in lieu of plantings in these areas.	-\$3,299
13	Provide cost savings for the deduction of all work related to the parking lot wayfinding monument sign including but not limited to sign, foundations, and electrical requirements.	-\$38,332
15	Provide cost savings for the deduction of all work related to the installation of wire mesh partitions as noted in specification 10 22 13 – Wire Mesh Partitions.	-\$30,386
16	Provide cost savings for the deduction of all work associated with the installation of ceramic floor tile as noted on the drawings.	-\$60,850
19	Provide cost savings for the deduction of all work associated with the modification of the phenolic lockers as noted in Home Locker Room CR12, First Aid/ Officials CR22, Locker Room BB22 and Locker Room SB22. Modifications shall include reducing overall locker height to 72” in lieu of 84”, side material thickness from 3/8” to 5/16”.	-\$10,750
24	Provide cost savings for the deduction of all work related to powder coating as noted in specification 13 12 60 - 2.3 Materials/Finishes - B. Substructure Finish. The grandstand substructure shall maintain a galvanized finish in lieu of galvanized and powered coated as noted in the specification.	-\$177,300
26	Provide cost savings for the deduction of all work related to the modification of the visitor bleacher as noted on A814 and throughout the drawings where shown.	-\$122,735

	Modifications shall assume the visitor bleacher remains but reduces the overall length and capacity of the visitor bleacher by approximately half. The visitor bleacher will maintain 8 seating rows typically spaced at 2'-6" as shown with the appropriate number of accessible seating spaces based on the new capacity calculation. This deduct only pertains to Bid Package 07.01 Bleachers.	
27	Provide cost savings for the deduction of all work associated with specification 13 12 50 – Transportable Bleacher. This deduct only pertains to Bid Package 07.01 Bleachers.	-\$21,890
32	Provide cost savings for the deduction of all work related to DDC scope and integration with the existing facility control systems. HVAC equipment shall be provided with local factory supplied controls only. All unit heaters will operate off integral thermostats and all split systems will operate off local programmable thermostatic controls. Outside air units shall be provided with factory supplied local controller. No monitoring, web system, or remote alarms will be provided.	-\$60,000
33	Provide cost savings for the deduction of all work associated with specification 27 51 00 – Public Address System.	-\$305,000
34	Provide cost savings for the deduction of all work associated with modification of specification 27 51 00 – Audiovisual Systems. Delete this specification completely along with Audio systems equipment noted on the system sheets. Specification has been replaced by 27 41 16.63 Sound Reinforcement System – Football and 27 41 16.73 Sound Reinforcement System – Baseball/Softball. Items to price in the project to complete systems shall include:	+\$34,090
34.1	¾" conduit from system rack in each press box (football, BB and SB) to above accessible ceiling for speaker cabling. Cabling by others.	Add Included In 34
34.2	¾" conduit from system rack in each press box (football, BB and SB) to the front counter for cabling to sound controls. Cabling by others.	Add Included In 34
34.3	2" conduit from each press box to connect to duct bank systems shown on the site plan for scoreboard fiber (fiber by others).	Add Included In 34
34.4	12 strand fiber from each facility (concessions IDF CR21, BB and SB pressbox back to the HS building through ductbanks shown on site plan as well as 12 Strand fiber from Concessions IDFCR21 to IDF CR04)	Add Included In 34
34.5	Install 60A, 120/208V/3ph, NEMA 3R panel with two (2) 40A/2p breakers, one(1) 30A/3p breaker and three (3) 20A/1p breakers for the scoreboard power. Scoreboard installer will make final connections from breakers to loads at the scoreboard and sound system. Panel shall be fed from panel HMDP in the concessions building, 60A/3p, feeder shall be (4) #3, (1) #8 in 2" conduit.	Add Included In 34
36	Contractor provided voluntary deduct from Original Bid Amount	-\$106,109

[END OF DOCUMENT]