

TOM CHESNUT
EXCAVATION & CONSTRUCTION, LLC
1794 HIGHBRIDGE RD.
LANCASTER, KY 40444

(859)229-1409 (859) 333-8080 (859)881-8983 (office/fax)
tcconstruction@windstream.net

CONTRACTORS BID

www.tcconcretelex.com

WORK TO BE PERFORMED AT:

TO: Fayette Co. Public Schools Division of Plant Operations 400 Springhill Drive Lexington, KY 40505	Leestown Middle School 2010 Leestown Rd. Lexington, KY
---	--

DATE: 09/27/2023	YOUR WORK ORDER NO.:	OUR BID NO.: 9163
-------------------------	-----------------------------	--------------------------

DESCRIPTION OF WORK TO BE PERFORMED

Concrete Curb Installation:

- Contractor to install 580 linear feet of curb 1' wide x 1' deep around the new modular building; curb will sit on top of the ground
- Contractor to excavate area to correct grade, form, pour, and finish the new concrete
- Concrete specifications: 4000 psi with fiber
- Concrete finish: broom
- Expansion material and saw cut control joints will be placed properly
- Concrete Cure N Seal sealer will be applied to concrete, this sealer is an acrylic sealer
- Edges will be backfilled with dirt
- Leestown Middle School to supply Contractor with water at no charge for project
- All debris from project will be hauled off site and disposed of properly
- Contractor to be paid in full within 30 days of project completion

COSTS: 580 linear feet @ \$35 per linear foot = \$20,300.00

TOTAL BID: \$20,300.00



Contractor Insured & Licensed.

All Material is guaranteed to be as specified, and the above work will be performed in accordance with the drawings and specifications provided for the above work and will be completed in a substantial workmanlike manner.

Tom Chesnut Excavation & Construction, LLC AUTHORIZED SIGNATURE:

**ACCEPTANCE
OF
PROPOSAL**

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above. Legal fees and court costs incurred in the collection of monies owed according to this contract will be borne by the customer. A service charge of 2% per month or 24% per annum will be added to all balances over 30 days. Contractor to be paid the day the project is completed.

Print Name _____

Signature _____

Date _____