

September 1, 2023

Larry Hellard
Utility Superintendent
Fayette County Public Schools

Re: Leestown Middle School Portable Area Drainage

Larry, we are pleased to provide an estimate to re-work site drainage north of the portable classroom. We intend to fill in a low area at the northeast corner and divert drainage to the west side of the football field. Also, provide above ground corrugated drain pipe at each downspout, as follows:

1. Provide underground utility location.
2. Temporary erosion control fencing.
3. Strip grass from the site to execute a positive drainage system.
4. Importing several triaxle loads of topsoil.
5. Seed/straw/fertilizer.
6. Install fittings at each downspout and connect approximately 15lf of solid corrugated drain pipe to the downspouts. Pipe to lay above ground to divert roof rain water from the building. Tubing from the AC units will be installed along the building to drain into downspouts.

NOTE –

1. We are not providing an engineer's review or drawing.
2. Work will be scheduled for the upcoming school fall break, however, wet weather could cause the work to be rescheduled.

TOTAL AMOUNT OF ESTIMATE = \$34,500.00

Please feel free to contact me with any questions. We appreciate this opportunity.

Thank you,
Bud Crolley 859 595-1624