



March 12, 2024

Hardin County Schools PAC  
Attn: Aaron Taylor  
384 W A Jenkins Rd.  
Elizabethtown, KY 42701

Quote # VLSQ650-04

Thank you for allowing Vincent Lighting Systems the opportunity to provide you with the attached budget proposal for the Hardin County Schools PAC. This proposed solution is based off our site visit and previous conversations regarding the facility.

**BASE QUOTE:                   \$ 540,600.00**

NOTE: Any applicable use or sales taxes have not been included in our proposal. If your project qualifies for tax exempt status, please forward a copy of your exemption certificate when placing the order.

Standard payment terms are 50% due at time of order, and balance due at time of shipment. For NET30 approved accounts, final progress payment will be invoiced at time of shipment. Prices referenced above are based on payment by cash, check, or ACH. Customers requiring the use of a credit card will incur a 3.0% processing charge added to prices above at time of credit card processing. All prices include standard ground freight allowed to the job site, FOB factory.

Unless noted above, these solutions do not include installation of the provided components.

Following this letter, you will find a bill of materials. These items will provide you a more detailed overview of our proposed solutions.

We appreciate the opportunity to provide you with these solutions. Our portfolio of trusted vendors, along with our 40+ years of experience, afford us the best tools to provide the best solutions for your project. As you review this proposal, please do not hesitate to reach out to me for any questions, clarifications, or changes that you need addressed.

Regards,

A handwritten signature in black ink, appearing to read 'Matt Hollstegge', written over a light blue horizontal line.

**Matt Hollstegge**  
**Account Executive**  
**859-488-4912**  
**[mhollstegge@vls.com](mailto:mhollstegge@vls.com)**





TECHNOLOGY FOR  
VISUAL ENVIRONMENTS

**BILL OF MATERIALS  
FOR  
HARDIN COUNTY PERFORMING ARTS  
CENTER NEW SYSTEM  
ELIZABETHTOWN, KY**

**Prepared On: 3/4/2024  
Quote # VLSQ350-04**

**PROJECT SALES**  
MATT HOLLSTEGGE  
MHOLLSTEGGE@VLS.COM  
859-488-4912

**PROJECT MANAGER**  
MATT HOLLSTEGGE  
MHOLLSTEGGE@VLS.COM  
859-488-4912

Project: Hardin County Performing Arts Center New System

Doc #: VLSQ350-04

Date: 3/4/2024

## BILL OF MATERIALS

Ln #	Qty	Part Number	Description
------	-----	-------------	-------------

### **BASE THEATRICAL SYSTEM**

#### **THEATRICAL DIMMER RACK**

1.	4	7141A1005-4	ETC 48-Module Sensor3 Rack
2.	4	7141A2006-4	ETC Sensor3 SR48 Rack Door- Black
3.	4	7140A1003	ETC Power Control Module
4.	60	7050A1003	ETC 20A Sensor3 Dual Dimmer Module 350 S
5.	132	7050A1185	ETC 20A Sensor3 Dual Relay Module
6.	28	7050A1202	ETC 20A Sensor3 Dual ThruPower Module 350 S
7.	2	7051A1105	ETC Sensor3 Bussing Kit
8.	1	7141K1002	ETC Sensor3 Sensor Phase Bar Fuse Tap Kit- Phase Loss
9.	16	HW6109	ETC Floor Mt ISO Vibration Pads NDB- Red
10.	1	1096A1112	ELTS2-1-M-3P-12 - Main Feed Three-phase 120/208 volt emergency lighting transfer switch with (12) 20 amp circuits in small NEMA1 cabinet

#### **DIMMER EQUIPMENT RACK (DER)**

11.	3	4268A1235	<b>NOTE:</b> <i>All equipment to be mounted in existing enclosure.</i> RSN-DMX4-T - Response Mk2 Four-port DMX/RDM Gateway <i>to include:</i> <i>- Four 3-pin terminal DMX connectors</i> <i>- Display and 4-button user interface</i> <i>- RJ45 Ethernet input</i> <i>- Black Finish</i>
12.	3	4268A1236	RSN-DMX4-T-RACK - Response Mk2 Four-port DMX/RDM Gateway <i>to include:</i> <i>- Four 3-pin terminal DMX connectors</i> <i>- Display and 4-button user interface</i> <i>- RJ45 Ethernet input</i> <i>- Black Finish</i> <i>- 1U Rack Mount Kit</i>
13.	1	PANEL1UVLS	1U Vincent Lighting Credit Panel
14.	2	24POESWITCH	Cisco SG350-28P 1U Network Switch
15.	2	BR1	1sp Panel w/Brush Grommet
16.	2	24PATPAN	1U 24-Port CAT5e Patch Panel
17.	48	2CAT5PATCHBK	2ft CAT5e Patch Cable- Black
18.	1	*UPS1000	2U Tripp Lite 1000VA/700W UPS
19.	1	PBL1	1sp Blank Panel- Black

#### **CONTROL RECEPTACLES**

20.	8	5105BL	Pathway RJ45 EtherCon Insert- Black
21.	6		<b>NOTE:</b> <i>To be inserted in existing location.</i> Pipe Mount DMX Output Receptacle

**Project: Hardin County Performing Arts Center New System**

Doc #: VLSQ350-04

Date: 3/4/2024

**BILL OF MATERIALS**

Ln #	Qty	Part Number	Description
		1094A1015	ETC 1G ECPB DMX Out Plug-in Station
		4100A1013	ETC DMX Prep Kit w/IDC Connector for CAT5/Solid Core
		1064A1023	ETC 2.5in(D) 1G Surface Mt Box
		2100A1302	ETC 1G & 2G ECPB Plug-in Station U-Bolt Kit
22.	4		Pipe Mount Dual DMX Output Receptacle
		1094A1015	(2) ETC 1G ECPB DMX Out Plug-in Station
		4100A1013	(2) ETC DMX Prep Kit w/IDC Connector for CAT5/Solid Core
		1064A1023	(2) ETC 2.5in(D) 1G Surface Mt Box
		2100A1302	ETC 1G & 2G ECPB Plug-in Station U-Bolt Kit
23.	2		Surface Mount DMX Output Receptacle
		1094A1015	ETC 1G ECPB DMX Out Plug-in Station
		4100A1013	ETC DMX Prep Kit w/IDC Connector for CAT5/Solid Core
		1064A1023	ETC 2.5in(D) 1G Surface Mt Box
			<b>BATTEN DATA DISTRIBUTION</b>
			<b>LOCATION:</b> <i>To be mounted at grid.</i>
24.	8		Surface Mount DMX Output Receptacle
		1094A1015	ETC 1G ECPB DMX Out Plug-in Station
		4100A1013	ETC DMX Prep Kit w/IDC Connector for CAT5/Solid Core
		1064A1023	ETC 2.5in(D) 1G Surface Mt Box
25.	8	WSCDMX5NB-100	TMB 100ft XLR5 Starcable Extension Cable
26.	8		Pipe Mount DMX Bypass
		1094A1131	ETC ECPB 'DMX Input' / 'DMX Output' Control Plug-in Station
		1064A1024	ETC 2.5in(D) 2G Surface Mt Box
		2100A1302	ETC 1G & 2G ECPB Plug-in Station U-Bolt Kit
			<b>FRONT LIGHT</b>
27.	28	7423A1010	ETC ColorSource Spot V ETL Engine Only w/Multiverse- Black w/Soft Focus Diffuser & Pattern Hold... <i>Fixture comes with power adaper, 5ft True1 extension or 10ft True1 extension. Specify cable at time of order.</i>
28.	21	7060A2001-K	ETC 10deg S4 Lens Tube- Black w/Color Frame
29.	7	7060A2047	ETC 26deg S4 EDLT Lens Tube- Black w/Color Frame
30.	28	MAB-ENGRAVED-VLS	TLS Mega-Clamp- Black
31.	28	SAFETYB	30in Safety Cable w/Spring Hook- Black
			<b>BACK CAT</b>
32.	6	7423A1010	ETC ColorSource Spot V ETL Engine Only w/Multiverse- Black w/Soft Focus Diffuser & Pattern Hold... <i>Fixture comes with power adaper, 5ft True1 extension or 10ft True1 extension. Specify cable at time of order.</i>
33.	6	7060A2000-K	ETC 5deg S4 Lens Tube- Black w/Color Frame

**Project: Hardin County Performing Arts Center New System**

Doc #: VLSQ350-04

Date: 3/4/2024

**BILL OF MATERIALS**

<b>Ln #</b>	<b>Qty</b>	<b>Part Number</b>	<b>Description</b>
34.	6	MAB-ENGRAVED-VLS	TLS Mega-Clamp- Black
35.	6	SAFETYB	30in Safety Cable w/Spring Hook- Black
<b>Balcony Rail</b>			
36.	16	7423A1010	ETC ColorSource Spot V ETL Engine Only w/Multiverse- Black w/Soft Focus Diffuser & Pattern Hold... <i>Fixture comes with power adaper, 5ft True1 extension or 10ft True1 extension. Specify cable at time of order.</i>
37.	16	7060A2046	ETC 19deg S4 EDLT Lens Tube- Black w/Color Frame
38.	16	MAB-ENGRAVED-VLS	TLS Mega-Clamp- Black
39.	16	SAFETYB	30in Safety Cable w/Spring Hook- Black
<b>TOP/BACK LIGHT</b>			
40.	28	7417A1011	ETC ColorSource Fresnel V- Black w/Multiverse <i>Fixture comes with power adaper, 5ft True1 extension or 10ft True1 extension. Specify cable at time of order.</i>
41.	28	MAB-ENGRAVED-VLS	TLS Mega-Clamp- Black
42.	28	SAFETYB	30in Safety Cable w/Spring Hook- Black
<b>SIDE LIGHT</b>			
43.	18	7423A1010	ETC ColorSource Spot V ETL Engine Only w/Multiverse- Black w/Soft Focus Diffuser & Pattern Hold... <i>Fixture comes with power adaper, 5ft True1 extension or 10ft True1 extension. Specify cable at time of order.</i>
44.	12	7060A2048	ETC 36deg S4 EDLT Lens Tube- Black w/Color Frame
45.	6	7060A2047	ETC 26deg S4 EDLT Lens Tube- Black w/Color Frame
46.	18	MAB-ENGRAVED-VLS	TLS Mega-Clamp- Black
47.	18	SAFETYB	30in Safety Cable w/Spring Hook- Black
<b>ADDITIONAL UNITS</b>			
48.	12	7423A1010	ETC ColorSource Spot V ETL Engine Only w/Multiverse- Black w/Soft Focus Diffuser & Pattern Hold... <i>Fixture comes with power adaper, 5ft True1 extension or 10ft True1 extension. Specify cable at time of order.</i>
49.	12	7060A2047	ETC 26deg S4 EDLT Lens Tube- Black w/Color Frame
50.	12	MAB-ENGRAVED-VLS	TLS Mega-Clamp- Black
51.	12	SAFETYB	30in Safety Cable w/Spring Hook- Black
<b>CYC LIGHTS</b>			
52.	7	SEV072	Elation Seven Batten 72
53.	14	MAB-ENGRAVED-VLS	TLS Mega-Clamp- Black

**Project: Hardin County Performing Arts Center New System**

Doc #: VLSQ350-04

Date: 3/4/2024

## **BILL OF MATERIALS**

<b>Ln #</b>	<b>Qty</b>	<b>Part Number</b>	<b>Description</b>
54.	14	SAFETYB	30in Safety Cable w/Spring Hook- Black
<b>MOVING LIGHTS</b>			
55.	6	2572A1200-B	HES Halcyon Titanium UB- Black
56.	6	2500B7029-A	ETC 6ft TRUE1(F) to Edison(M) Power Cable
57.	12	MWB	TLS Mega-Claw- Black
58.	6	SAFETYB	30in Safety Cable w/Spring Hook- Black
<b>PORTABLE CABLE</b>			
59.	10	WSCDMX5NB-5	TMB 5ft XLR5 Starcable Extension Cable
60.	50	WSCDMX5NB-10	TMB 10ft XLR5 Starcable Extension Cable
61.	70	WSCDMX5NB-15	TMB 15ft XLR5 Starcable Extension Cable
62.	10	WSCDMX5NB-25	TMB 25ft XLR5 Starcable Extension Cable
63.	10	ZSJO123TNAC25	TMB 25ft 12/3 SJO PowerCON Extension Cable
64.	15	ZSJO123TNAC15	TMB 15ft 12/3 SJO PowerCON Extension Cable
65.	15	ZSJO123TNAC10	TMB 10ft 12/3 SJO PowerCON Extension Cable
66.	10	ZSJO123TNAC5	TMB 5ft 12/3 SJO PowerCON Extension Cable

### **SUPPLIER SERVICES**

- Ground freight shipping included.
- Set of electronic submittals, including a bill of materials, product data sheets and installation shop drawings.
- Job site meeting with contractor prior to installation, to review system design and answer any installation questions.
- The services of a qualified field technician to start-up the system and train personnel in its proper operation and maintenance are included. When the installation is nearing completion, please fill-out the commissioning form, found in the front of the submittal, and send it back to the Vincent Lighting project manager allowing at least three weeks lead time to schedule our field technician.
- End user training to consist of an initial four hour session, at a time mutually agreed upon between owner and VLS.
- All Lifts, Ladders, or equipment required to access Vincent Supplied equipment are to be provided by the Electrical Contractor or End User.
- Final termination of low voltage control, wiring which has been supplied, installed, and tagged by the electrical contractor at equipment listed in this Bill of Materials. VLS Terminations to exclude houselight fixtures on the field side and any Fiber Optic cabling.
- All items will be warranted to be free from defects in materials and workmanship for a period of 24 months from the date of system turn-on and owner's acceptance. This warranty is exclusive of normal wear and tear. Vincent Lighting is not responsible for the cost of the removal, shipment to Vincent Lighting for repair, or re-installation of returned serviced or replacement warranty equipment.
- For possible warranty repair returns, we recommend you retain some manufacturers shipment cartons for

**Project: Hardin County Performing Arts Center New System**

Doc #: VLSQ350-04

Date: 3/4/2024

## BILL OF MATERIALS

Ln #	Qty	Part Number	Description
------	-----	-------------	-------------

larger or odd sized equipment.

- Seven-day-a-week, toll-free service line and online support ticket portal at <https://vlshelp.freshdesk.com/support/tickets/new>.

### TERMS & CONDITIONS

All shipments are FOB factory, ground freight allowed to the jobsite. Freight claims must be filed directly with the shipper. Any product shortages must be reported to the Vincent Lighting project manager within 72 hours from time of delivery. Any claims thereafter will not be honored.

Unless evidence of tax exempt status is provided, Vincent Lighting Systems may charge sales tax for items shipped to destinations in the following states: Arkansas, Colorado, Indiana, Kentucky, Michigan, North Carolina, Ohio, Pennsylvania, Vermont, Virginia, and West Virginia. For orders shipped to other states, you are solely responsible to report & pay for all taxes, including use tax if applicable, to the Department of Revenue of your state. You can contact your respective taxing authority for detailed information.

This order will be purchased in accordance with our Bill of Materials and quotation. Receipt of your purchase order for the agreed amount signifies acceptance of the quoted terms. There shall be no modification to terms without written acceptance by Vincent Lighting Systems.

The Bill of Materials and pricing are based on our interpretation of the drawings, plans and specifications received in this office and represent a system using components that fulfill the design intent of the project. Orders placed for the above referenced project shall be "as per Vincent Lighting Bill of Materials".

Payment terms are net 30 days on approved accounts. A service charge of 2% per month will be applied to all invoices not paid within 30 days. If you wish to open an account, please fill out the enclosed credit application. If you do not intend to pay sales tax, please furnish us with a signed tax-exempt certificate. Return the forms to Shelley Hammond, Credit Manager, by fax at (216) 475-6376 or email at [shammond@vls.com](mailto:shammond@vls.com).

It is Vincent Lighting Systems' policy to request a copy of the Notice of Commencement filed with the County Recorder, if required by the state within the project is located. If applicable, Vincent Lighting Systems will serve a Notice of Furnishing to the Owner and Prime Contractor at the appropriate time. The actual requests will be mailed separately via certified mail.

The equipment will be ordered on a hold for release basis. Submittal drawings for approval will take approximately 6-8 weeks. Manufacturing time will be approximately 30 to 90 days after approval and written release. Release for manufacture and shipment of all equipment is required within 120 calendar days after receipt of order. It is Vincent Lighting Systems' policy that orders not properly released within this period are subject to a 2% per month increase. Orders placed and subsequently canceled where either as-built or submittal drawings have been started or the purchase of special materials is required, will be assessed a cancellation charge of 25% of the quoted price for the order or actual costs incurred, whichever is greater.

**END OF BILL OF MATERIALS DOCUMENT**