



POWELL'S

ASPHALT SEALING & STRIPING LLC

Estimate

DATE March 19, 2024

975 Sand Lick Rd
Greensburg, Ky 42743
270-849-5173

Invoice # 1559

Mercer County Board of Education

Prepared by: William Powell

Estimate for excavation and patching at High School parking

Excavate 295 cubic yards out of the heavy-duty school bus driving lane. Install 8" of stone, 4" of Compacted asphalt Base and 2" of compacted asphalt Surface in 8 different patches. In the 2 lite duty driving lanes we will excavate 95 cubic yards, install 6" stone, 2" compacted asphalt Base and 2" compacted asphalt Surface in 4 different patches to repair base failure. In the remaining patches as well as the exit roadway we will mill around the perimeter of each patch and install 3" compacted asphalt Surface. Restripe anything that is disturbed.

Total \$163,980.00

Since the school is tax exempt the Mago Harrodsburg plant request the school to set up account with Tax exempt status if not already on file.

This price is good for 30 days.

Acceptance

Date

If you have any questions concerning this estimate please contact William Powell, 270-849-5173,
Email bpowell444@yahoo.com