#### Wehr Constructors Inc - Louisville OFFICE AND YARD 2517 Plantside Dr Louisville, KY 40299

Owner's Signature



#### GENERAL CONTRACTORS ADDRESS CORRESPONDENCE TO: 2517 Plantside Dr Louisville, KY 40299

Date

PHONE: 502-491-9250 FAX: 502-493-8653

		CHANGI	3 OR	DER REQUE	2ST	
Date:	11/1	3/2024		Project Name:	W	Vest Hardin Middle School
То:	65 W	lin County Board of Education V A Jenkins Road		Architect Proje	ect N	o. 202280
	Eliza	abethtown, KY 42701		Wehr Project 1	No.	24-049
Attn:	John	Stith				
	Re:	Wehr Request No. <u>CO 3</u>				
		ON OF CHANGE: itable Soils at Pond				
For the	above	change, we would add the amount of \$65,365 change, we would add the amount of \$271,50 change, we would add the amount of \$315,67	1.38 to	o the contract for the contract for	r Opt r Opt	ion 1B.
T.		9.1				
	<i>em</i>	Subcontractor  Diviling Prothers Construction				Subtotal
	$\frac{1}{2}$	Phillips Brothers Construction  Construction Manager Fee				\$64,260.20 \$1,105.28
	z otal	Total Cost				\$65,365.48
		I				
Ite	em	Subcontractor				Subtotal
	1	Phillips Brothers Construction				\$266,910.52
	2	Construction Manager Fee				\$4,590.86
To	otal	Total Cost				\$271,501.38
Ite	em	Subcontractor				Subtotal
	1	Phillips Brothers Construction				\$310,335.58
,	2	Construction Manager Fee				\$5,337.77
To	otal	Total Cost				\$315,673.35
				W		R CONSTRUCTORS, INC.  By
We hav	ve revi	ewed the above Change Order Request and it is	s 🗖	Approved; $\Box$	Reje	ected;  to be Revised & Resubmitted.
Arcl	hitect's	s Signature Co.	 mpany	y Name		Date
We hav	ve revi	ewed the above Change Order Request and it is		Approved;	Reie	ected;  to be Revised & Resubmitted.

Company Name

Rev. 11/7/2024



West Hardin Middle School Re: PR 003 - Unsuitable Soils at Pond

#### PR-003 Pricing Breakdown:

#### Areas Breakdown

Area 1 - 110'x130'x8'

Length	Width	Depth	Volume	Volume
(feet)	(feet)	(feet)	(cubic feet)	(cubic yard)
110	130	8	114400	4237.04

un	it price	unit		extended
	_			
\$	28.00	CY	\$	118,637.04
-		~ .	-	,

Option 1A - Dirt fill from on-site

	Option 1B - DGA (stone) fill				
unit price unit			extended		
\$	70.00	CY	\$	296,592.59	

Option 2 - Class II channel lining, #2 stone, TX-130, DGA				
unit price	unit	extended		
\$ 79.00	CY	\$ 334,725.93		

Area 2 - 21 X96 X2				
Length	Width	Depth	Volume	Volume
(feet)	(feet)	(feet)	(cubic feet)	(cubic yard)
21	96	2	4032	1/0 33

Option 1A				
ıu	nit price	unit		extended
\$	28.00	CY	\$	4,181.33

	Option 1B					
ur	it price	unit		extended		
\$	70.00	CY	\$	10,453.33		

Option 2				
unit price	unit		extended	
\$ 79.00	CY	\$	11,797.33	

\*\*A \$64,400.00 credit will apply to for the original undercut allowance included in the base bid\*\*


Total (before credit)	\$ 122,818.37
Total (after credit)	\$ 58,418.37

Total (before credit) \$ 307,045.93 Total (after credit) \$ **242,645.93**  Total (before credit) \$ 346,523.26 Total (after credit) \$ 282,123.26

Total including 10% OHP = \$64,260.20

Total including 10% OHP = \$266,910.52

Total including 10% OHP = \$310,335.58



Reference Image from PR-003 and Solid Ground's Report

## **Proposal Request**

PROJECT: (name and address)
West Hardin Middle School
Cecilia, KY

OWNER: (name and address)
Hardin County Board of Education
65 W. A. Jenkins Road
Elizabethtown, KY 42701

CONTRACT INFORMATION:

Contract For: General Construction

Date: 8/22/2024

ARCHITECT: (name and address)

JRA Architects 301 E. Vine Street Lexington, KY 40507 Architect's Project Number: 202280 Proposal Request Number: 003 Proposal Request Date: 10/30/2024

**CONTRACTOR**: (name and address)

Wehr Constructors, Inc. 2517 Plantside Drive Louisville, KY 40299

The Owner requests an itemized proposal for changes to the Contract Sum and Contract Time for proposed modifications to the Contract Documents described herein. The Contractor shall submit this proposal within Zero (0) days or notify the Architect in writing of the anticipated date of submission.

(Insert a detailed description of the proposed modifications to the Contract Documents and, if applicable, attach or reference specific exhibits.)

On site, Solid Ground Consulting Engineering, has identified that at the Pond Area, the proposed 2' undercut material to be inadequate for Tensar use. Added remdiation needed to bridge over softer than expected material with high organics. Contractor to provide pricing for 2 options noted below.

#### Option #1

Recommend undercutting to elevation 698.0' where a firm red clay was encountered. Place engineered fill in a 12-18" loose lift at the bottom of the undercut (target compaction of 92%) Place engineered fill in 8-12" loose lifts up to 5 feet below subgrade elevation (target compaction of 95%) Place engineered fill in maximum 8" loose lifts to subgrade elevation at 98%

#### Option #2

Undercut to elevation 703.0' place channel liner to #2 stone in 6-8" lifts and walk into subgrade until the subgrade accepts no additional stone.

Place a layer of TX-130 geogridd, capped with 8" of DGA.

Place engineered fill in maximum 8" loose lifts to subgrade elevation at 98% compaction.

THIS IS NOT A CHANGE ORDER, A CONSTRUCTION CHANGE DIRECTIVE, OR A DIRECTION TO PROCEED WITH THE WORK DESCRIBED IN THE PROPOSED MODIFICATIONS.

#### REQUESTED BY THE ARCHITECT:


D. Robert Deal, AIA, President
PRINTED NAME AND TITLE



**Company:** Solid Ground Consulting Engineers **Title:** 24-527 WHMS 241009 E - Phillip Brothers

**Contact:** Shane Smith **Group:** Owner: Hardin Co Schools

Email: Shanesmith@solidgroundce.com No. Items: 4



### **Summary:**

Created: Wed, 10/9/2024

Solid Ground rep was on site today to observe two areas with unsuitable material, as highlighted in the drawings.

## (2) Discrepancy Log

• West Hardin Middle School 24-527

	Discrepancy	Corrective Action
DISCREPANCY (1) DATE:24-10-09	Pond area proposed 2' undercut showed material to be inadequate for Tensar use. Added remediation needed to bridge over softer than expected material with high Organics.	Awaiting final approval  Date Resolved:
DISCREPANCY (2) DATE:24-10-09	21'96' section of the southeast area of the building pad topsoil was observed at 2'x	Date Resolved:
DISCREPANCY (3) DATE:	N/A	Date Resolved:

Created: Wed, 10/23/2024

Discrepancy log.





**Company:** Solid Ground Consulting Engineers **Title:** 24-527 WHMS 241009 E - Phillip Brothers

**Contact:** Shane Smith **Group:** Owner: Hardin Co Schools

Email: Shanesmith@solidgroundce.com No. Items: 4



## Pond Area Recommendation Created:

Wed, 10/9/2024

701.50' material firm enough to hold a D6 dozer. 698' firm material with traces of reddish clays observed.

#### Option #1:

We recommend undercutting to elevation 698.0' where a firm red clay was encountered Place engineered fill in a 12-18" loose lift at the bottom of the undercut (target compaction of 92%) Place engineered fill in 8-12" loose lifts up to 5 feet below subgrade elevation (target compaction of 95%) Place engineered fill in maximum 8" loose lifts to subgrade elevation at 98%.

#### Option #2:

Undercut to elevation 703.0' place channel liner to #2 stone in 6-8" lifts and walk into subgrade until the subgrade accepts no additional stone.

Place a layer of TX-130 geogrid, capped with 8" of DGA.

Place engineered fill in maximum 8" loose lifts to subgrade elevation at 98% compaction.





**Company:** Solid Ground Consulting Engineers **Title:** 24-527 W

**Contact:** Shane Smith

**Phone:** 502-338-4173

**Email:** Shanesmith@solidgroundce.com

**Title:** 24-527 WHMS 241009 E - Phillip Brothers

**Group:** Owner: Hardin Co Schools

**Created:** Wed, 10/9/2024

No. Items: 4



# Southeast Section Of Building Pad

Created:

Wed, 10/9/2024

Top soil observed to be 2' deep. Elevation of suitable material observed at 700'.