

ESTIMATE

Trussted LLC
1835 Nature Ln SE
Corydon, IN 47112

Joshua@gotrussted.com
+1 (812) 225-6389
HTTP://www.gotrussted.com



Anchorage School: Anchorage Public School

Bill to

Anchorage School
11400 Ridge Rd
Anchorage, KY 40223

Estimate details

Estimate no.: 1181

Estimate date: 02/07/2025

#	Product or service	Description	Qty	Rate	Amount
1.	Labor	Phase 2 Remove all white wall cabinets across wall. In other classroom, remove countertop from base cabinets, remove two base cabinets from location of french door, remove electrical from area of french door, cut opening in wall for french door, install door, finish walls where cabinets were removed, repair, and paint. Install new countertop. Patch flooring in front of french door.	1	\$9,275.00	\$9,275.00
2.	Material	Flooring for under two base cabinets being removed, new laminate countertop, paint, and mud supplies.	1	\$1,875.00	\$1,875.00
3.	Material	Option 1: 3068 double french door (total width of both doors combined is 3 feet) Full glass, spring hinges, and ball catch closures. (This can be modified to preference)	1	\$1,275.00	\$1,275.00
4.	Labor and material	Option 2: Install a 3068 pocket door with a standard wooden door slab. This includes demoing additional wall to install pocket door.	1	\$2,450.00	\$2,450.00
5.	Labor and material	Option 3: Install a 6068 double French door	1	\$3,250.00	\$3,250.00

(combined width of both doors is a total width of 6 feet)
This includes labor to cut additional wall and door/door install.

6.	Note	This estimate assumes that we won't discover mechanicals in the wall when cutting out the French door. If we do find mechanicals, we'll ask the customer for their advice on how to proceed before we resume the work.	\$0.00	\$0.00
----	-------------	--	--------	--------

Total	\$18,125.00
--------------	--------------------

Accepted date	Accepted by
----------------------	--------------------