

ESTIMATE



Service Address

Powell County,
Middle School
Stanton, KY

Prepared For

Tekton
99 Windhaven Drive,
suite3
Nicholasville, KY
40356
(859) 894-2286

Hemenway Concrete Const, INC.

194 Industry Pky
Nicholasville, KY 40356
Phone: (859) 621-4356
Email: mark@hemenway-concrete.com
Fax: (866) 228-0504
Web: www.hemenway-concrete.com

Estimate # 1394
Date 09/02/2025
Business / Tax # 20-0955379

Description

Total

Surface Prep \$28,350.00

Approximately 8,100 sq ft of area requires grinding off existing self-leveling cement compound. We will make multiple passes in all directions to level out low and high spots and achieve a tolerance of 1/8" within a 10' span (FL 35). We will use a 10' straight edge to continuously check the tolerance levels during the grinding process. After a four-step grind, we will likely apply a grout coat to fill pinholes, followed by grinding off the grout coat and applying a floor hardener/densifier to prepare the surface for flooring crew fasteners. We estimate 6-7 days to complete this work. Our plan is to grind the existing cement floor level and to grind down enough material to meet specifications.



Additional labor. \$1,250.00

We plan to use a pallet jack to move all wood flooring materials to one end, allowing us to grind over half of the area. Once that area is complete, we will move the flooring materials to the finished side and repeat the process for the remaining area.

| | |
|---|------------|
| General Requirement | \$2,500.00 |
| Mobilize equipment to the indoor Gymnasium, and set up. | |
| 6-7 days of traveling to and from Stanton, KY. | |

| | |
|-----------------|--------------------|
| Subtotal | \$32,100.00 |
| Total | \$32,100.00 |

Normally we collect approx. 30% down once work has started.
Balance upon completion.

30Percent due upon work commencement.

all work is guaranteed to be in tolerances with all standard concrete practices.

All material is guaranteed to be used with the manufacturer recomendations.

finial payment is due shortly after completion.

1-15 days preferred.

Tekton