

North Todd Elementary Addition / Renovation
A & K Construction, Inc. Project No. 1326-10
Proposal #5 Revised2
JKS # 2009007 (BG #09-291)
2/21/11

Water main relocation

Per request of JKS Architects (see attached)

1. Relocated Existing Water Main

See Attached

Division	Contractor	Labor/Equip	Material	Total
1 Utilities	Eagle Fire Protection	\$ 5,394.60	\$ 3,582.99	\$ 8,977.59
Sub-Total		\$ 5,394.60	\$ 3,582.99	\$ 8,977.59
Overhead/Profit				\$ 1,347.41
Total				\$ 10,325.00

A Division of Stewart-Richey Const. Co., Inc.
2137 Glen Lily Rd.
Bowling Green, Ky 42101
(270)843-4172
Fax: (270)782-6654

CHANGE ORDER #1

Date: 2/11/11
To: A&K Con.
Attn: Rickey Tabers
Project Name: North Todd Elementary
Project Location

The following revision becomes part of, and in conformance with, the existing contract.
Relocate 6" combination water line around new building pad. (approx. 160')

Labor: 60 hrs @ \$77.41 _____ \$4,644.60

Materials: _____ \$3,582.99

Equipment: _____ \$750.00

CHANGE ORDER AMOUNT _____ \$8,977.59

Add for removing existing water line under building pad: \$1,660.00

Estimator's Signature: _____ Date: _____

Acceptance of Change Order by my signature below, I acknowledge the above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified under same terms and conditions as specified in original contract unless otherwise specified.

Acceptance Signature: _____ Date: _____

All material to be as specified. All work is to be completed in a workmanlike manner according to standard practice. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above this proposal price. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workmen's Compensation insurance. A certificate of insurance is available upon request.

Ricky A. Tabers

Subject: FW: North Todd Water Main Relocation

From: Mark Kinslow [mailto:mkinslow@stewarttrichey.com]

Sent: Monday, February 21, 2011 2:36 PM

To: Ricky A. Tabers; 'Roddy Grimes'

Subject: RE: North Todd Water Main Relocation

Ricky

The list of materials that I had figured for the relocation are as follows

160' of 6" C-900

1- 6" 90

1- 6" 45

160' of tracer wire

50 ton of crushed stone

This runs us to the new location of the fire hydrant. From the fire hydrant in was under the original scope of work.

Thanks Mark