



Snap Painting Plus LLC

1860 Williamson Ct.

Louisville, KY 40223

Office: 502-408-4433

stclair@snappaintingplus.com

PROPOSAL

Contact Details:

Name: Anchorage Classroom Ceiling 106 + Admin Building

Project Location: 11400 Ridge Rd./ Louisville, KY / 40219

Project Details:

Paint Included In Price: YES

Date: 3-26-26

Material Picked Up By: Snap Painting Plus

Project Notes: Painting

1. Before and after each day that the project is considered to be “working” Snap Painting Plus will set up drop clothes and/or site protection throughout the premises. Snap Painting Plus will clean up before and after each “working” day.
2. All paint and primer to be supplied by Snap Painting Plus. Color selections determined by plans.
3. All miscellaneous materials (drops, masking paper/plastic, and tape) included in the price.
4. For information about what is included in your project see details below.

SEE PAGE 2

Area Details:

Work Areas:

CLASSROOM 106:

- Provide floor protection
- We will supply the following materials: ¼" drywall, drywall mud, drywall screws, and sanding block
- Anchorage School to provide: ½" drywall (in storage) and finish ceiling paint (in storage)
- Apply ½" and ¼" drywall to fur out to level of existing ceiling
- Drywall mud and texture to as closely match the existing texture as possible
- Priming and painting the entire ceiling

LABOR: \$1600.00

Material: \$200.00

TOTAL: \$1800.00

Superintendent's Office:

- Remove plastic trim borders off the ceiling panels
- Painting entire ceiling including drywall and glued on panels (ceiling white - paint color)
- Spackle holes in walls before painting
- Paint all walls - color to be Alabaster
- Prime and paint all trim and doors Blue

Labor: \$1600.00

Paint Material: \$300.00

TOTAL: \$1,900.00

Conference Room:

--Remove plastic trim borders off the ceiling panels

--Painting entire ceiling including drywall and glued on panels (ceiling white - paint color)

- Paint all walls - color to be Alabaster

-Prime and paint all trim and doors Blue

Labor: \$1200.00

Material: \$300.00

TOTAL: \$1,500.00

I am going to pass on the option of scraping and make the walls smooth in this area

-Conference Room Built-In cabinets:

-Labor: \$1,200.00

Material: \$200.00

TOTAL: \$1,400.00

Hallway off conference room:

--Painting entire ceiling including drywall and glued on panels (ceiling white - paint color)

- Paint all walls - color to be Alabaster

-Prime and paint all trim and doors blue

Labor: \$800.00

Material: \$150.00

TOTAL: \$950.00

CFO's OFFICE:

-Paint all walls alabaster

-Paint ceiling (ceiling white paint color)

-Paint trim and doors blue

Labor: \$1200.00

Material: \$300.00

TOTAL: \$1500.00

Diana's/Pat's Office:

--Remove plastic trim borders off the ceiling panels

-Painting entire ceiling including drywall and glued on panels (ceiling white - paint color)

-Painting of all green walls throughout to new color - Alabaster

-Prime and paint trim and doors blue

Labor: \$1600.00

Material: \$300.00

TOTAL: \$1,900.00

Christy's Office:

--Remove plastic trim borders off the ceiling panels

-Painting entire ceiling including drywall and glued on panels (ceiling white - paint color)

-Painting all walls included to blue (will need exact color)

-Painting of door/frame and window trim included - WHITE (Faced off to Christy's side)

Labor: \$2000.00

Material: \$400.00

TOTAL: \$2,400.00

Jane's Office:

- Remove plastic trim borders off the ceiling panels
- Painting entire ceiling including drywall and glued on panels (ceiling white - paint color)
- Painting of all walls - Alabaster
- Painting of trim and doors - blue

Labor: \$1,600.00

Material: \$300.00

TOTAL: \$1,900.00

MAIN HALLWAY:

- Painting of entire ceiling (glued up panels) - color to be ceiling white
- Painting of all walls - colors to be alabaster
- To be painted ceiling white
- Painting of all trim and doors blue

Labor: \$3,600.00

Material: \$800.00

TOTAL: \$4,400.00

HALLWAY WOMEN'S BATHROOM:

- Repair drywall texture at ceiling
- Paint the entire ceiling - color to be ceiling white
- Paint all walls - color to be alabaster
- No painting of trim here (tile) but painting of door/frame blue included

Labor: \$1600.00

Material: \$200.00

TOTAL: \$1800.00

HALLWAY MEN'S BATHROOM:

-No ceiling painting (acoustical ceiling)

-Paint all walls - color to be alabaster

-No painting of trim here (tile) but painting of door/frame blue included

Labor: \$1200.00

Material: \$150.00

TOTAL: \$1350.00

HILLARY'S OFFICE:

-Painting of entire ceiling (glued up panels) - color to be ceiling white

-Painting of all walls - colors to be alabaster

-To be painted ceiling white

-Painting of all trim and doors blue

Labor: \$1600.00

Material: \$250.00

TOTAL: \$1850.00

COMBINED PRICING:

TOTAL FOR ALL ABOVE:

LABOR: \$20,800.00

PAINT MATERIAL/MISC MATERIAL: \$3,850.00

TOTAL: \$24,650.00

Material Counts (Estimated) - these are included in the price (for reference only)

-20-25 gallons of standard ceiling paint

-35-40 gallons of wall paint - Mult-Apply Semi-gloss (Alabaster)

-5 gallons of bonding primer (for rubber trim)

-7-8 gallons of trim/doors paint - Mult-Apply Semi-gloss (Blue color - need color name)

-Miscellaneous material: Drywall mud, caulk, rosin paper for floors, painters tape, painters plastic, rollers.