



# Proposal

1264 Liberty Road • Beaver Dam, KY 42320

PROPOSAL SUBMITTED TO	JOB NAME	JOB #
ADDRESS	JOB LOCATION Walking Trail	DATE 5/8/2026
PHONE #	FAX #	ARCHITECT

We hereby submit specifications and estimates for:

Site 5: Stabilize Lake so it won't breach while works done. Replace existing 15" pipe with 2 18" dual wall pipes to allow maximum flow & prevent overflow washing out walking trail. Place dense grade & remove damaged asphalt. Create keyway to prevent underflow. Replace all removed asphalt w/ 4" concrete. Once cured, remove lake stabilization to put water level back to normal pool.  
Total \$6,210<sup>00</sup>

Site 6: Install 48" x 40' plastic dual wall after removing existing box culvert. Remove 110' x 10' damaged asphalt & replace w/ 4" concrete. Place flowable fill under 15" side drain to prevent underflow.  
Total 28,775<sup>00</sup>

We propose hereby to furnish material and labor - complete in accordance with above specifications, for the sum of:

\$ 31,985<sup>00</sup> Dollars

with payments to be made as follows: PAID IN FULL @ THE COMPLETION OF EACH SITE

Any alteration or deviation from above specifications involving extra costs will be executed only upon written order, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control.

Respectfully submitted

Note: This proposal may be withdrawn by us if not accepted within 30 days.

## Acceptance of Proposal

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature \_\_\_\_\_

Date of Acceptance: \_\_\_\_\_

Signature \_\_\_\_\_



# Proposal

1264 Liberty Road • Beaver Dam, KY 42320

PROPOSAL SUBMITTED TO <i>Dino Co Parks</i>	JOB NAME	JOB #
ADDRESS <i>2300 ST RT 69N Harford Ky 47347</i>	JOB LOCATION <i>Walking Trail</i>	
PHONE	DATE <i>5/8/2026</i>	DATE OF PLANS <i>Upon Approval</i>
FAX #	ARCHITECT	

We hereby submit specifications and estimates for:

**Site 1:** To Remove 48" Culvert 3. Replace with 60" x 20' Dual Wall Pipe. Remove 40' x 10' Damaged Asphalt 3. Replace w/ 4" CONCRETE. Place Rip Rap For Erosion Control on Slopes.  
Total \$10,325<sup>00</sup>

**Site 2:** Remove 3. Replace 18" x 30' dual wall culvert. Remove 46' x 10' of Damaged Asphalt 3. Replace w/ 4" concrete. Place Rip Rap on Slopes.  
Total \$8,489<sup>00</sup>

**Site 3:** Remove Existing 24" Culverts 3. Replace w/ 36" x 30' Dual wall pipes. (2) Remove 50' x 10' Damaged Asphalt 3. Replace w/ 4" concrete. Place Rip Rap on Up 3. Down Stream Slopes.  
Total \$13,185<sup>00</sup>

**Site 4:** Replace 24" Culvert w/ 36" x 40' Dual Wall pipe. Remove 25' x 10' Damaged Asphalt 3. Replace w/ 4" concrete. Place Rip Rap For Erosion Control.  
Total \$9,518<sup>00</sup>

\* See Next Page For Site 5 3 Site 6 \*

We propose hereby to furnish material and labor - complete in accordance with above specifications, for the sum of:

\$ \_\_\_\_\_ Dollars

with payments to be made as follows: \_\_\_\_\_

Any alteration or deviation from above specifications involving extra costs will be executed only upon written order, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control.

Respectfully submitted \_\_\_\_\_

Note: This proposal may be withdrawn by us if not accepted within \_\_\_\_\_ days.

## Acceptance of Proposal

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature \_\_\_\_\_

Date of Acceptance: \_\_\_\_\_

Signature \_\_\_\_\_



# Proposal

1264 Liberty Road • Beaver Dam, KY 42320

PROPOSAL SUBMITTED TO	JOB NAME	JOB #
ADDRESS	JOB LOCATION Rosine Park	
	DATE 5/8/2026	DATE OF PLANS Upon Approval
PHONE #	FAX #	ARCHITECT

We hereby submit specifications and estimates for:

Site 1: Install 24" Dual Wall culvert. Remove 30' x 10' Damaged Asphalt & Replace w/ 4" concrete. Clean Up & Downstream Ditch Debris Approx 50' Each Way. Place Rip Rap For Stabilization.  
Total 6284<sup>00</sup>

Site 2: Remove Rusted Out Culvert & Replace with 2- 48" x 30' Dual Wall pipes. Remove 30' x 10' Damaged Asphalt & Replace w/ 4" concrete. Place Keyway To Reenter Underflow & Place Rip Rap For Stabilization.  
Total 24,915<sup>00</sup>

We propose hereby to furnish material and labor - complete in accordance with above specifications, for the sum of:

\$ 31,199<sup>00</sup> Dollars

with payments to be made as follows: In Full upon Completion of Each Site.

Any alteration or deviation from above specifications involving extra costs will be executed only upon written order, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control.

Respectfully submitted

Note: This proposal may be withdrawn by us if not accepted within 30 days.

## Acceptance of Proposal

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature \_\_\_\_\_

Date of Acceptance: \_\_\_\_\_

Signature \_\_\_\_\_